

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐
(HIGHLIGHT CHANGES)

APPLICATION FOR PERMIT TO DRILL			5. MINERAL LEASE NO. N/A	6. SURFACE Private
1A. Type of Work: DRILL <input checked="" type="checkbox"/> REENTER <input type="checkbox"/> DEEPEN <input type="checkbox"/>			7. IF INDIAN, ALLOTTEE OR TRIBE NAME: N/A	
B. Type of Well: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER: SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/>			8. UNIT or CA AGREEMENT NAME: N/A Drunkards Wash	
2. NAME OF OPERATOR: Phillips Petroleum Company			9. WELL NAME and NUMBER: Schmidt 29-531	
3. ADDRESS OF OPERATOR: 6825 South 5300 West, P.O. Box 851, Price, Utah 84501 CITY STATE ZIP			PHONE NUMBER: (435) 613-9777	10. FIELD AND POOL, OR WILDCAT: Undesignated Drunkards Wash
4. LOCATION OF WELL (FOOTAGES) AT SURFACE: 1803' FSL, 2148' FWL AT PROPOSED PRODUCING ZONE: 4280556 Y 39,57647 514918X -110.82631			11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NE/4 SW/4 Section 29, T14S, R10E, SLB&M	
14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE: 1.6 miles southwest of Price, UT			12. COUNTY: Carbon	13. STATE: UTAH
15. DISTANCE TO NEAREST PROPERTY OR LEASE LINE (FEET) 470'	16. NUMBER OF ACRES IN LEASE: N/A	17. NUMBER OF ACRES ASSIGNED TO THIS WELL: 160 acres		
18. DISTANCE TO NEAREST WELL (DRILLING, COMPLETED, OR APPLIED FOR) ON THIS LEASE (FEET) 1500'	19. PROPOSED DEPTH: 1300' 1626'	20. BOND DESCRIPTION: Rotary		
21. ELEVATIONS (SHOW WHETHER DF, RT, GR, ETC.) 5608.2' GR	22. APPROXIMATE DATE WORK WILL START: September 2002	23. ESTIMATED DURATION:		
24. PROPOSED CASING AND CEMENTING PROGRAM				
SIZE OF HOLE	CASING SIZE, GRADE, AND WEIGHT PER FOOT	SETTING DEPTH	CEMENT TYPE, QUANTITY, YIELD, AND SLURRY WEIGHT	
14"	12 3/4" Conductor	40'	63 sks G+2&CaCl+1/4#/sk flocl	
11"	J-55 8 5/8" 24#/ft	163'	121 sks 50/50poz8%gel+2%CaCl+1%extender	
7 7/8"	N-80 5 1/2" 17#/ft	1616'	74 sks "G" thixotropic	

25. **ATTACHMENTS**

VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION RULES:

- | | |
|--|--|
| <input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER | <input checked="" type="checkbox"/> COMPLETE DRILLING PLAN |
| <input checked="" type="checkbox"/> EVIDENCE OF DIVISION OF WATER RIGHTS APPROVAL FOR USE OF WATER | <input type="checkbox"/> FORM 5, IF OPERATOR IS PERSON OR COMPANY OTHER THAN THE LEASE OWNER |

Name & Signature: Jean Semborski

Jean Semborski

Title: Permitting Analyst

Date: 7/22/02

(This space for state use only)

API Number Assigned:


43-007-30863

Approved by the
Utah Division of
Oil, Gas and Mining

Approval:


Date: 09-04-02

By:



Township 14 South

Range 10 East



- Legend**
- Drill Hole Location
 - ⊙ Metal Cap (Found)
 - Brass Cap (Searched for, but not found)
 - △ Rock Pile
 - () GLO
 - GPS Measured

NOTES:
1. UTM AND LATITUDE / LONGITUDE COORDINATES ARE DERIVED USING A GPS PATHFINDER AND ARE SHOWN IN NAD 27 DATUM.

LAT / LONG
39°34'37"N
110°49'12"W

Location:
THE WELL LOCATION WAS DETERMINED USING A TRIMBLE 4700 GPS SURVEY GRADE UNIT.

Basis of Bearing:
THE BASIS OF BEARING IS GPS MEASURED.

GLO Bearing:
THE BEARINGS INDICATED ARE PER THE RECORDED PLAT OBTAINED FROM THE U.S. LAND OFFICE.

Basis of Elevation:
BASIS OF ELEVATION OF 5552' BEING AT THE SOUTHEAST SECTION CORNER OF SECTION 29, TOWNSHIP 14 SOUTH, RANGE 10 EAST, SALT LAKE BASE AND MERIDIAN, AS SHOWN ON THE PRICE QUADRANGLE 7.5 MINUTE SERIES MAP.

Description of Location:
PROPOSED DRILL HOLE LOCATED IN THE NE1/4 SW1/4 OF SECTION 29, T14S, R10E, S.L.B.&M., BEING 1803.08' NORTH AND 2147.61' EAST FROM THE SOUTHWEST SECTION CORNER OF SECTION 29, T14S, R10E, SALT LAKE BASE & MERIDIAN.


Surveyor's Certificate:

I, Albert J. Spensko, a Registered Professional Land Surveyor, holding Certificate 146652 State of Utah, do hereby certify that the information on this drawing is a true and accurate survey based on data of record and was conducted under my personal direction and supervision as shown hereon.






TALON RESOURCES, INC.
375 S. Carbon Ave., Ste 101, (A-10)
Price - Huntington, Utah
Phone (435)637-8781 Fax (435)636-8603
E-Mail talon@castlenet.com



PHILLIPS PETROLEUM
WELL #29-531
Section 29, T14S, R10E, S.L.B.&M.
Carbon County, Utah


Drawn By: J. STANSFIELD	Checked By: L.W.J./A.J.S.
Drawing No. A-1	Date: 07/09/02
	Scale: 1" = 1000'
Sheet 1 of 4	Job No. 671



**PHILLIPS PETROLEUM COMPANY**

6825 South 5300 West
P.O. Box 851
Price, UT 84501
TEL: (435) 613-9777 FAX: (435) 613-9782

July 22, 2002



Ms Diana Mason
State of Utah
Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
SLC, Utah 84114-5801

RE: Application for Permit to Drill-
Schmidt 29-531, NE/4 SW/4 Sec.29
T14S, R10E, SLB & M, Carbon County, Utah

Dear Ms. Mason:

Enclosed is the original of the *Application for Permit to Drill* (APD). Included with the APD is the following information:

- Exhibit "A"- Survey Plat of the Proposed Well Site;
- Exhibit "B" - Proposed Location Map with Pipeline, Power, and Road Access;
- Exhibit "C" - Drilling Site Layout;
- Exhibit "D" - Drilling Information
- Exhibit "E" - Multipoint Surface Use Plan
- Exhibit "F" - Typical Road Cross-section;
- Exhibit "G" - BOP Diagram;
- Exhibit "H" - Typical Wellhead Manifold;
- Exhibit "I" - Evidence of Bond;

ORIGINAL

CONFIDENTIAL

This proposed well is located more than 460' from the boundary of the Unit Area and from the boundary of any uncommitted tract within the Unit Area and will not require the administrative approval in accordance with Utah Administrative Code Rule R649-3-3.

Please accept this letter as Phillips Petroleum Company's written request for confidential treatment of all information contained in and pertaining to this permit application, if said information is eligible for such consideration.

Thank you very much for your timely consideration of this application. Please feel free to contact me if you have any questions.

Sincerely,

A handwritten signature in cursive script, reading "Jean Semborski".

Jean Semborski
Permitting Analyst

cc: Mr. Eric Jones, BLM, Moab, Utah
Mr. Gene Herrington, Texaco
Ms. Julie Bennett, Dominion Resources
Mr. Don Stephens, BLM, Price, Utah
Ms. Jeanette Borges, Phillips Petroleum Company
Mrs. Deanna Walker, Phillips Petroleum Company
Mr. Mark Jones, DOGM, Price, Utah
PPCo Well File



PHILLIPS PETROLEUM COMPANY

Insurance, Real Estate and Claims
P.O. Box 105
Livermore, Colorado 80536

July 26, 2002

File: UT/Carbon 109; 29-531 Well
Paul R. Schmidt, et.ux.

Diana Mason
State of Utah Department of Natural Resources
Division of Oil, Gas and Mining
Oil and Gas Program
1594 West North Temple, Suite 1210
Salt Lake City, Utah 84114-5801

Dear Ms. Mason:

Phillips Petroleum Company plans to drill the 29-531 natural gas well, which will be located in the Southwest One-quarter of Section 29, Township 14 South, Range 10 East, S.L.B.&M., Carbon County, Utah. Phillips has filed an Application for Permit to Drill (APD) with the Division of Oil, Gas and Mining for this well.

Pursuant to the State of Utah Division of Oil, Gas and Mining, Oil and Gas Conservation General Rules, R659-3-34 ("Well Site Restoration Rule"), Phillips entered into a surface use agreement with the surface owner of the pad location for this well. The agreement includes an agreement for reclamation of the subject surface property and well site restoration. Enclosed is an Affidavit Concerning Surface Use Agreement evidencing Phillips' agreement with the surface owner for this well.

Please advise Jean Semborski with Phillips or me if you have questions or require additional information from Phillips regarding the subject surface use agreement.

Sincerely,

Deanna J. Walker
Phone: 970-498-9677
Fax: 970-498-9687
E-mail: dwalker@ppco.com

Enc.

cc: Jean Semborski, Phillips Petroleum Company

RECEIVED

AUG 05 2002

DIVISION OF
OIL, GAS AND MINING

**AFFIDAVIT CONCERNING
SURFACE USE AGREEMENT**

STATE OF COLORADO }
 }
COUNTY OF LARIMER }

DEANNA J. WALKER, being first duly sworn upon her oath, deposes and says:

1. I am a senior real estate specialist in the Insurance, Real Estate and Claims department of Phillips Petroleum Company, a Delaware corporation, duly authorized to transact business in the State of Utah, ("Phillips") and am authorized to execute this Affidavit on behalf of said corporation.
2. Paul Robert Schmidt and Alice P. Schmidt ("Surface Owner") own the surface estate of property described as follows ("Property"):

Township 14 South, Range 10 East, S.L.B.&M.
Carbon County, Utah:

Section 29:

NE1/4SW1/4;

Also beginning at a point 750 feet North of the South ¼ corner of said section,

Thence North 570 feet,

Thence West 1320 feet,

Thence South 570 feet,

Thence East 1320 feet to the point of beginning.

Less Parcels 02-1673-0002, Boo, 168, Page 663 and
02-1673-0004, Book 454, Page 481.


Less Carbon County Road.

3. Phillips owns or operates oil and gas rights, including mineral leases, and may become holder of other oil and gas rights, including mineral leases, underlying and in the vicinity of the Property ("Leases") and desires to enter on the Property for the purposes of conducting oil and gas operations related to such oil and gas rights, including mineral leases.
4. Phillips entered into a Surface Use and Damage Agreement effective as of the 1st day of July, 2002 with the Surface Owner covering the Property. In addition to other agreements and as required by the State of Utah Division of Oil, Gas and Mining, Oil and Gas Conservation General Rules, R649-3-34 ("Well Site Restoration Rule"), the Surface Use and Damage Agreement sets forth the agreement between Phillips and the Surface Owner for reclamation of the Property and well site restoration for the surface pad location for Phillips' 29-531 well and associated infrastructure, which will be located on

the Property. A Memorandum of Surface Use and Damage Agreement will be filed in the public records of Carbon County, Utah.

5. I execute and record this affidavit in accordance with the requirements of the Well Site Restoration Rule.
6. The matters stated herein are true of my own knowledge, except to any matters stated herein upon information and belief, and, as to those matters, I believe them to be true.

DATED this 26th day of July, 2002.



DEANNA J. WALKER
Phillips Petroleum Company
Senior Real Estate Specialist

Subscribed, sworn and acknowledged to and by Deanna J. Walker before me this 26th day of July, 2002.



NOTARY PUBLIC
For the State of Colorado

My Commission Expires:

October 15, 2005




EXHIBIT "D"
DRILLING PROGRAM

Attached to Form 3
Phillips Petroleum Company
Schmidt 29-531
NE/4, SW/4, Sec.29, T14S, R10E, SLB & M
1803' FSL, 2148' FWL
Carbon County, Utah

1. The Surface Geologic Formation

Mancos Shale

2. Estimated Tops of Important Geologic Markers

Blue Gate/Ferron 1186'

3. Projected Gas & H2O zones (Ferron Formation)

Coals and sandstones 1216' - 1326'

No groundwater is expected to be encountered.

Casing & cementing will be done to protect potentially productive hydrocarbons, lost circulation zones, abnormal pressure zones, and prospectively valuable mineral deposits. All indications of usable water will be reported.

Surface casing will be tested to 1400 psi.

4. The Proposed Casing and Cementing Programs

<u>HOLE SIZE</u>	<u>SETTING DEPTH (INTERVAL)</u>	<u>SIZE (OD)</u>	<u>WEIGHT, GRADE & JOINT</u>	<u>NEW, USED</u>
14"	40'	12-3/4"	Conductor	New
11"	163'	8-5/8"	24#ST&C	New
7-7/8"	1616'	5-1/2	17#LT&C	New

Cement Program -Every attempt will be made to bring cement back to surface.

Surface Casing: 63 sks G+2%CaCl+1/4#per sack floccel;15.8#/gal,density, 1.15 cu.ft/sk yield.

Production Casing: 121 sks 50/50 poz 8%gel +2%CaCl+10%extender;12.5#/gal, density, 1.92 cu.ft/sk yield.

74 sks "G" thixotropic, 14.2#/gal density, 1.61 cu.ft/sk yield

The following shall be entered in the driller's log:

- 1) Blowout preventer pressure tests, including test pressures and results;
- 2) Blowout preventer tests for proper functioning;
- 3) Blowout prevention drills conducted;
- 4) Casing run, including size, grade, weight, and depth set;
- 5) How the pipe was cemented, including amount of cement, type, whether cement circulated, location of the cementing tools, etc.;
- 6) Waiting on cement time for each casing string;
- 7) Casing pressure tests after cementing, including test pressures and results.

5. The Operator's Minimum Specifications for Pressure Control

Exhibit "G" is a schematic diagram of the blowout preventer equipment. A double gate 3000 psi BOPE will be used with a rotating head. This equipment will be tested to 2000 psi. All tests will be recorded in a Driller's Report Book. Physical operation of BOP's will be checked on each trip.

6. The Type and Characteristics of the Proposed Circulating Muds

0-300	11" hole	Drill with air, will mud-up if necessary.
300-TD	7 7/8" hole	Drill with air. 400 psi @ 1500-1800 Scf.

7. The Testing, Logging and Coring Programs are as followed

300-TD Gamma Ray, Density, Neutron Porosity, Induction, Caliper

Any Anticipated Abnormal Pressures or Temperatures

No abnormal pressures or temperatures have been noted or reported in wells drilled in the area nor at the depths anticipated in this well. Bottom hole pressure expected is 704 psi max. No hydrogen sulfide or other hazardous gases or fluids have been found, reported or are known to exist at these depths in the area.

8. Anticipated Starting Date and Duration of the Operations.

The well will be drilled around September 2002.

Verbal and/or written notifications listed below shall be submitted in accordance with instructions from the Division of Oil, Gas & Mining:

- (a) prior to beginning construction;
- (b) prior to spudding;
- (c) prior to running any casing or BOP tests;
- (d) prior to plugging the well, for verbal plugging instructions.

Spills, blowouts, fires, leaks, accidents or other unusual occurrences shall be reported to the Division of Oil, Gas & Mining immediately.

EXHIBIT "E"
MULTIPOINT SURFACE USE PLAN

Attached to Form 3
Phillips Petroleum Company
Schmidt 29-531
NE/4, SW/4, Sec.29, T14S, R10E, SLB & M
1803' FSL, 2148' FWL
Carbon County, Utah

1. Existing Roads

- a. We do not plan to change, alter or improve upon any existing state or county roads.
- b. Existing roads will be maintained in the same or better condition. See Exhibit "B".

2. Planned Access

Approximately 800' of new access is required (See Exhibit "B")

- a. Maximum Width: 24' travel surface with 27' base
- b. Maximum grade: 6%
- c. Turnouts: None
- d. Drainage design: 6 culverts may be required. Water will be diverted around well pad as necessary.
- e. If the well is productive, the road will be surfaced and maintained as necessary to prevent soil erosion and accommodate year-round traffic.
- f. Pipe and Power lines will follow the proposed access road.

3. Location of Existing Wells

- a. See Exhibit "B". There are 4 proposed and 3 existing wells within a one-mile radius of the proposed location.

4. Location of Existing and/or Proposed Facilities

- a. If the well is a producer, installation of production facilities will be as shown on Exhibit "H". Buried powerlines run along access on the east and north, gathering lines on the south or west.
- b. Rehabilitation of all pad areas not used for production facilities will be made in accordance with landowner stipulations.

5. Location and Type of Water Supply

- a. Water to be used for drilling will be purchased from the Price River Water Improvement District (a local source of municipal water) (tel. 435-637-6350).
- b. Water will be transported by truck over approved access roads.
- c. No water well is to be drilled for this location.

6. Source of Construction Materials

- a. Any necessary construction materials needed will be obtained locally and hauled to the location on existing roads.
- b. No construction or surfacing materials will be taken from Federal/Indian land.

7. Methods for handling waste disposal

- a. As the well will be air drilled, a small reserve pit will be constructed with a minimum of one-half the total depth below the original ground surface on the lowest point within the pit. The pit will not be lined unless conditions encountered during construction warrant it or if deemed necessary by the DOGM representative during the pre-site inspection. Three sides of the reserve pit will be fenced within 24 hours after completion of construction and the fourth side within 24 hours after drilling operation cease with woven wire topped with barbed wire to a height of not less than four feet. The fence will be kept in good repair while the pit is drying.
- b. Following drilling, the liquid waste will be evaporated from the pit and the pit back-filled and returned to natural grade. No liquid hydrocarbons will be discharged to the reserve pit or location.
- c. In the event fluids are produced, any oil will be retained in tankage until sold and any water produced will be retained until its quality can be determined. The quality and quantity of the water will determine the method of disposal.
- d. Trash will be contained in a portable metal container and will be hauled from location periodically and disposed of at an approved disposal site. Chemical toilets will be placed on location and sewage will be disposed of at an appropriate disposal site.

8. Ancillary Facilities

- a. We anticipate no need for ancillary facilities with the exception of one trailer to be located on the drill site.

9. Wellsite Layout

- a. Available topsoil will be removed from the location and stockpiled. Location of mud tanks, reserve and berm pits, and soil stockpiles will be located as shown on the attachments.
- b. A blooie pit will be located 100' from the drill hole. A line will be placed on the surface from the center hole to the pit. The pit will not be lined, but will be fenced on four sides to protect livestock/wildlife.
- c. Access to the well pad will be as shown on Exhibit "B".
- d. Natural runoff will be diverted around the well pad.

10. Plans for Restoration of Surface

- a. All surface areas not required for producing operations will be graded to as near original condition as possible and contoured to maintain possible erosion to a minimum.
- b. Available topsoil will be stockpiled and will be evenly distributed over the disturbed areas and the area will be reseeded as prescribed by the landowner.
- c. Pits and any other area that would present a hazard to wildlife or livestock will be fenced off when the rig is released and removed.

11. Surface Ownership:

- a. The wellsite and access road will be constructed on lands owned by Paul R. and Alice P. Schmidt . The operator shall contact the landowner representative and the Division of Oil, Gas and mining 48 hours prior to beginning construction activities.
Land Owner Contact Information:
Paul R. and Alice P. Schmidt
676 West 1800 South
Price, Utah 84501-4422
(435) 637-1006

12. Other Information:

- a. The primary surface use is farming and grazing. The nearest dwelling is approximately 800 feet Southwest.
- b. Nearest live water is Drunkards Wash located at 800' north.
- c. If there is snow on the ground when construction begins, it will be removed before the soil is disturbed and piled downhill from the topsoil stockpile location.
- d. The backslope and foreslope will be constructed no steeper than 4:1.
- e. All equipment and vehicles will be confined to the access road and well pad.
- f. A complete copy of the approved Application for Permit to Drill (APD) including conditions and stipulations, shall be on the wellsite during construction and drilling operations

There will be no deviation from the proposed drilling and/or workover program without prior approval from the Division of Oil, Gas & Mining.

13. Company Representative

Jean Semborski
Permitting Analyst
Phillips Petroleum Company
6825 S. 5300 W. P.O. Box 851
Price, Utah 84501
(435) 613-9777
(435) 820-9807

Mail Approved A.P.D. To:

Company Representative


Excavation Contractor

Nelco Contractors Inc.
Larry Jensen
(435) 637-3495
(435) 636-5268




14. Certification

I hereby certify that I, or persons under my direct supervision have inspected the proposed drillsite and access route; that I am familiar with the conditions which presently exist; that the statements made in this plan are, to the best of my knowledge, true and correct, and that the work associated with the operations proposed herein will be performed by Phillips Petroleum Company and its subcontractors in conformity with this plan and the terms and conditions under which it is approved.

7/23/02
Date


Jean Semborski
Permitting Analyst
Phillips Petroleum Company

ELEVATION OF UNGRADED GROUND AT LOCATION STAKE = 5608.2'
 ELAVATION OF GRADED GROUND AT LOCATION STAKE = 5607.7'




TALON RESOURCES, INC.


375 S. Carbon Ave., Ste 101, (A-10)
 Price, Utah 84501
 Phone (435)637-8781 Fax (435)636-8603
 E-Mail taloncastlenet.com

**PHILLIPS PETROLEUM
 LOCATION LAYOUT
 Section 29, T14S, R8E, S.L.B.&M.
 WELL #29-531**



Drawn By: J. STANSFIELD	Checked By: L.W.J.
Drawing No. A-2	Date: 07/09/02
	Scale: 1" = 50'
Sheet 2 of 4	Job No. 671



$1" = 10'$
 X-Section
 Scale
 $1" = 40'$



SLOPE = 1 1/2 : 1
 (EXCEPT PIT)
 PIT SLOPE = 1 : 1



TALON RESOURCES, INC.

375 S. Carbon Ave., Ste 101, (A-10)

Price, Utah 84501

Phone (435) 637-8781 Fax (435) 636-8603

E-Mail talon@castlenet.com

PHILLIPS PETROLEUM
 TYPICAL CROSS SECTION
 Section 29, T14S, R8E, S.L.B.&M.
 WELL #29-531

Drawn By: J. STANSFIELD	Checked By: L.W.J.
Drawing No. C-1	Date: 07/09/02
	Scale: 1" = 40'
Sheet 3 of 4	Job No. 671

APPROXIMATE YARDAGES


CUT

(6") TOPSOIL STRIPPING = 750 CU. YDS.

REMAINING LOCATION = 3,830 CU. YDS.

TOTAL CUT = 4,330 CU. YDS.

TOTAL FILL = 800 CU. YDS.



LEGEND

Proposed Well Location:
 Other Proposed Well Locations:
 Proposed Powerline:
 Proposed Pipeline:
 Proposed Roads:
 Lease Boundary:
 Existing Wells:



Scale: 1" = 2000'

July 16, 2002


PHILLIPS PETROLEUM COMPANY

6825 South 5300 West
 P.O. Box 851
 Price, Utah 84501
 Phone: (435) 613-9777
 Fax: (435) 613-9782



WELL # 29-531
 Section 29, T14S, R10E, S.L.B.&M.
 Exhibit B 1 of 2

APPROXIMATE LAYOUT OF RIG & EQUIPMENT



40'

PIPE TRAILER

HOLE
○

40'

FUEL TANK

DOG HOUSE

BOOSTER

COMPRESSOR

FRAC TANK

45'

RIG

8'

SURFACE
CUTTINGS
PIT


20'

AUX
COMP.


MAIN
PIT

PHILLIPS PETROLEUM COMPANY


WELL SITE LAYOUT (235' x 175')



TYPICAL ROAD CROSS-SECTION




DIVERTER HEAD



- (1) 2" 5M FLANGED CHOKE
- (2) 2" 5M GATE VALVE (FLANGED)
- (3) 2" 5M STUDDED CROSS
- (4) 2" 5M GATE VALVE (FLANGED)
- (5) 2" 5M FLANGED CHOKE
- (6) 2" 5M GATE VALVE (FLANGED)
- (7) 2" LINE
- (8) 2" 5M GATE VALVE (FLANGED)
- (9) 3000# GAUGE

NOTE:

NUMBER 8 GATE VALVE SITS ON TOP OF MANIFORD BETWEEN STUDDED CROSS AND 3000# GAUGE.



MANIFOLD

AmSouth Bank
Post Office Box 11007
Birmingham, Alabama 35288 USA
(800) 284-4100
Telex: 6823023
S.W.I.F.T.: AMSBUS44

International Division

AMSOUTH

PAGE 2
DATED: AUGUST 17, 2001
OUR REF: 78317150

EACH DRAFT HEREUNDER MUST BE LISTED AND ENDORSED ON THE REVERSE SIDE OF THE LETTER OF CREDIT AND THIS LETTER OF CREDIT MUST BE ATTACHED TO THE LAST DRAFT WHEN THE CREDIT HAS BEEN EXHAUSTED.


DRAFTS MAY BE PRESENTED AT OUR OFFICE, INTERNATIONAL DEPARTMENT, 250 RIVERCHASE PARKWAY SOUTH, 3RD FLOOR, MOOVER, ALBAMA 35244 NO LATER THAN 2:00 P.M. (LOCAL TIME) ON AUGUST 17, 2002, AND BEAR THE CLAUSE "DRAWN UNDER AMSOUTH BANK, LETTER OF CREDIT NO. 78317150 DATED AUGUST 17, 2001."

THIS LETTER OF CREDIT SHALL BE DEEMED AUTOMATICALLY EXTENDED FOR A PERIOD ON ONE YEAR FROM THE CURRENT OR ANY FUTURE EXPIRATION DATE HEREOF, UNLESS AT LEAST 90 (NINETY) DAYS PRIOR TO SUCH EXPIRATION DATE, WE NOTIFY YOU THAT WE HAVE ELECTED NOT TO EXTEND THIS LETTER OF CREDIT FOR SUCH ADDITIONAL PERIOD.

WE HEREBY ENGAGE WITH THE BONA FIDE HOLDERS OF ANY DRAFT AND/OR DOCUMENTS PRESENTED UNDER AND IN COMPLIANCE WITH THE TERMS OF THIS LETTER OF CREDIT THAT SUCH DRAFT AND/OR DOCUMENTS WILL BE DULY HONORED UPON PRESENTATION TO US. OUR OBLIGATIONS HEREUNDER SHALL NOT BE SUBJECT TO ANY CLAIM OR DEFENSE BY REASON OF THE INVALIDITY, ILLEGALITY, OR UNENFORCEABILITY OF ANY OF THE AGREEMENTS UPON WHICH THIS LETTER OF CREDIT IS BASED.

THIS CREDIT IS SUBJECT TO THE UNIFORM CUSTOMS AND PRACTICE FOR DOCUMENTARY CREDITS (1994 REVISION), INTERNATIONAL CHAMBER OF COMMERCE PUBLICATION NUMBER 500.

AMSOUTH BANK


AUTHORIZED SIGNATURE
INTERNATIONAL BANKING OFFICER

AMSOUTH BANK


AUTHORIZED SIGNATURE
VICE PRESIDENT

003

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 07/29/2002

API NO. ASSIGNED: 43-007-30863

WELL NAME: SCHMIDT 29-531

OPERATOR: PHILLIPS PETROLEUM (N1475)

CONTACT: JEAN SEMBORSKI

PHONE NUMBER: 435-613-9777

PROPOSED LOCATION:

NESW 29 140S 100E

SURFACE: 1803 FSL 2148 FWL

BOTTOM: 1803 FSL 2148 FWL

CARBON

DRUNKARDS WASH (48)

LEASE TYPE: 4 - Fee

LEASE NUMBER: FEE

SURFACE OWNER: 4 - Fee

PROPOSED FORMATION: FRSD

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering	DKD	9/3/2002
Geology		
Surface		

LATITUDE: 39.57647

LONGITUDE: 110.82631

RECEIVED AND/OR REVIEWED:


- ☒ Plat
- ☒ Bond: Fed[] Ind[] Sta[] Fee[4]
(No. 78317150)
- ☒ Potash (Y/N)
- ☒ Oil Shale 190-5 (B) or 190-3 or 190-13
- ☒ Water Permit
(No. MUNICIPAL)
- ☒ RDCC Review (Y/N)
(Date:)
- ☒ Fee Surf Agreement (Y/N)

LOCATION AND SITING:

- ___ R649-2-3.
- Unit DRUNKARDS WASH ☒
- ___ R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells
- ___ R649-3-3. Exception
- ___ Drilling Unit
Board Cause No: 243-2
Eff Date: 7-13-99
Siting: * 400' fr Unit boundary & uncomm. tract
- ___ R649-3-11. Directional Drill

COMMENTS: Need Permit (Rec'd 8-12-02)

STIPULATIONS: 1 - STATEMENT OF BASIS




OPERATOR NAME: PHILLIPS PETRO (N1475)

SEC: 29 T14S R10E

FIELD: DRUNKARDS WASH (48)

COUNTY: CARBON SPACING: 243-2



Utah Oil Gas and Mining

Field Status

- ABANDONED
- ACTIVE
- COMBINED
- INACTIVE
- PROPOSED
- STORAGE
- TERMINATED
- Township.shp
- Sections

Well Status

- * Gas Injection
- * Gas Storage
- * Location Abandoned
- ⊙ Location
- * Plugged
- * Producing Gas
- * Producing Oil
- * Shut-In Gas
- * Shut-In Oil
- x Temporarily Abandoned
- * Test Well
- * Water Injection
- * Water Supply
- * Water Disposal

Unit Status

- EXPLORATORY
- GAS STORAGE
- NF PP OIL
- NF SECONDARY
- PENDING
- PI OIL
- PP GAS
- PP GEOTHERML
- PP OIL
- SECONDARY
- TERMINATED



Prepared By: D. Mason
Date: 30-July-2002

09-02 Phillips Schmidt 29 '31

Casing Schematic

Surface

M94103

8-5/8"
MW 8.4
Frac 13.

TOC @
8.

Surface
163. MD

TOC @
381.

BOP
BHP

$(0.052)(8.4)(1626) = 710 \text{ psi}$
Anticipated = 704 psi

3M BOP proposed

Adequate prev 9/3/2002

1186' -
Blue Gate/Frac

1204'
TOC Trail

1216'

roals 55's

1326'

5-1/2"
MW 8.4

Production
1626. MD

Well name:	09-02 Phillips Schmidt 29-531	
Operator:	Phillips Petroleum Company	Project ID:
String type:	Surface	43-007-30863
Location:	Carbon County	

Design parameters:
Collapse

Mud weight: 8.400 ppg
Design is based on evacuated pipe.

Minimum design factors:
Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 65 °F
Bottom hole temperature: 67 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 130 ft

Cement top:

8 ft

Burst

Max anticipated surface pressure: 0 psi
Internal gradient: 0.436 psi/ft
Calculated BHP 71 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on air weight.
Neutral point: 142 ft

Non-directional string.

Re subsequent strings:

Next setting depth: 1,626 ft
Next mud weight: 8.400 ppg
Next setting BHP: 710 psi
Fracture mud wt: 13.000 ppg
Fracture depth: 163 ft
Injection pressure 110 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost ()
1	163	8.625	24.00	J-55	ST&C	163	163	7.972	1068

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	71	1370	19.26	71	2950	41.47	4	244	62.37 J

↓
BHP @ 7 cogs

Prepared by: Dustin Doucet
Utah Dept. of Natural Resources

Phone: 801-538-5281
FAX: 801-359-3940

Date: September 3, 2002
Salt Lake City, Utah

ENGINEERING STIPULATIONS: NONE

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Collapse is based on a vertical depth of 163 ft, a mud weight of 8.4 ppg The casing is considered to be evacuated for collapse purposes.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:	09-02 Phillips Schmidt 29-531	
Operator:	Phillips Petroleum Company	Project ID:
String type:	Production	43-007-30863
Location:	Carbon County	

Design parameters:
Collapse

Mud weight: 8.400 ppg
Design is based on evacuated pipe.

Minimum design factors:
Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 65 °F
Bottom hole temperature: 88 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 250 ft

Cement top:

381 ft

Burst

Max anticipated surface pressure: 0 psi
Internal gradient: 0.436 psi/ft
Calculated BHP: 710 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Non-directional string.

Tension is based on air weight.
Neutral point: 1,419 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost ()
1	1626	5.5	17.00	N-80	LT&C	1626	1626	4.767	11664

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	710	6290	8.87	710	7740	10.91	28	348	12.59 J

Prepared by: Dustin Doucet
Utah Dept. of Natural Resources

Phone: 801-538-5281
FAX: 801-359-3940

Date: September 3, 2002
Salt Lake City, Utah

ENGINEERING STIPULATIONS: NONE

Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Collapse is based on a vertical depth of 1626 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

DIVISION OF OIL, GAS AND MINING
APPLICATION FOR PERMIT TO DRILL
STATEMENT OF BASIS

OPERATOR: Phillips
WELL NAME & NUMBER: Schmidt 29-531
API NUMBER: 43-007-30863
LOCATION: 1/4, 1/4 NESW Sec: 29 TWP: 14S RNG: 10E 1803 FSL 2148 FWL

Geology/Ground Water:

A silty, poorly-permeable soil is developed on a thin veneer of Quaternary Slope Wash covering the Blue Gate Shale Member of the Mancos Shale. No aquifers with high quality ground water are likely to be encountered. The proposed casing and cement program will adequately isolate any water-bearing strata. Many water rights have been filed within a mile of the location but not on any water wells.

Reviewer: Christopher J. Kierst **Date:** 8/21/2002

Surface:

Proposed location is ~2 miles South of Price, Utah. The direct area drains to the North into Drunkards Wash and then East to the Price River, a year-round live water source. Drunkards wash lies ~.25 mile North of proposed location. The Carbon Canal lies south of the location ~.25 mile. The location is proposed on existing agricultural ground and the area directly surrounding the proposed well location is used for agricultural purposes as well. The soil is a clay loam and will be erosive when disturbed. Proposed access will be from the North from the proposed Mettler well crossing Drunkards Wash onto the Schmidt property. Paul and Andy Schmidt, surface owners, were present during the on-site. Talk was also made during the on-site to ensure the fencing would be adequate for livestock as well as protect the privacy of the property.

Reviewer: Mark L. Jones **Date:** August 20, 2002

Conditions of Approval/Application for Permit to Drill:

1. Culverts as needed where crossing drainages sufficient to handle run-off.
2. Berm the location and pit to deflect runoff from entering location and prevent any drilling and/or production fluids from leaving the location.
3. Construction of location and access road as per discussion during on-site evaluation.
4. A synthetic liner with a minimum thickness of 12 mils shall be properly installed and maintained in the reserve pit.

ON-SITE PREDRILL EVALUATION
Division of Oil, Gas and Mining

OPERATOR: Phillips
WELL NAME & NUMBER: Schmidt 29-531
API NUMBER: 43-007-30863
LEASE: Fee FIELD/UNIT: _____
LOCATION: 1/4, 1/4 NESW Sec: 29 TWP: 14S RNG: 10E 1803 FSL 2148 FWL
LEGAL WELL SITING: 460 F unit boundary and uncommitted tracts.
GPS COORD (UTM): X = 514916 E; Y = 4380564 N SURFACE OWNER: Paul Schmidt.

PARTICIPANTS

M. Jones (DOGM), J. Semborski (Phillips), L. Jensen (NELCO), Paul and Andy Schmidt (surface).

REGIONAL/LOCAL SETTING & TOPOGRAPHY

Proposed location is ~2 miles South of Price, Utah. The direct area drains to the North into Drunkards Wash and then East to the Price River, a year-round live water source. Drunkards wash lies ~.25 mile North of proposed location. The Carbon Canal lies south of the location ~.25 mile. The location is proposed on existing agricultural ground and the area directly surrounding the proposed well location is used for agricultural purposes as well. The soil is a clay loam and will be erosive when disturbed. Proposed access will be from the North from the proposed Mettler well crossing Drunkards Wash onto the Schmidt property.

SURFACE USE PLAN

CURRENT SURFACE USE: Grazing and farming activities.

PROPOSED SURFACE DISTURBANCE: 235' x 175' and a 50' x 50' x 10' pit.

LOCATION OF EXISTING WELLS WITHIN A 1 MILE RADIUS: 4 proposed gas wells and 4 producing gas wells are within a 1 mile radius of the above proposed well.

LOCATION OF PRODUCTION FACILITIES AND PIPELINES: Along roadside.

SOURCE OF CONSTRUCTION MATERIAL: Obtained locally and transported in.

ANCILLARY FACILITIES: None anticipated.

WASTE MANAGEMENT PLAN:

Portable chemical toilets which will be emptied into the municipal waste treatment system; garbage cans on location will be emptied into centralized dumpsters which will be emptied into an approved landfill. Crude oil production is unlikely. Drilling fluid, completion / frac fluid and cuttings will be buried in the pit after evaporation and slashing the pit liner. Produced water will be gathered to the evaporation pit and eventually injected into the Navajo Sandstone via a salt-water disposal well. Used oil from drilling operations and support is hauled to a used oil recycler and reused.

ENVIRONMENTAL PARAMETERS

AFFECTED FLOODPLAINS AND/OR WETLANDS: Drunkards wash is located ~.25 mile North of the location. Mr. Schmidt has a quite extensive runoff collection system that catches all runoff from his farm, gathers it via piping into one pond, which is then pumped back to the top of the farm to be re-used for irrigation purposes. Any fluids leaving the location would eventually make it to this collection system.

FLORA/FAUNA: Prime Carbon County hay ground.

SOIL TYPE AND CHARACTERISTICS: Clay loam.

EROSION/SEDIMENTATION/STABILITY: Moderately erosive upon disturbance.

PALEONTOLOGICAL POTENTIAL: None observed.

RESERVE PIT

CHARACTERISTICS: Dugout earthen pit.

LINER REQUIREMENTS (Site Ranking Form attached): Liner required.

SURFACE RESTORATION/RECLAMATION PLAN

As per surface use agreement.

SURFACE AGREEMENT: Has been signed.

CULTURAL RESOURCES/ARCHAEOLOGY: Will be done prior to drilling.

OTHER OBSERVATIONS/COMMENTS

Talk was also made during the on-site to ensure the fencing would be adequate for livestock as well as protect the privacy of the property.

ATTACHMENTS

Photos of this location were taken and placed on file.

Mark L. Jones
DOGM REPRESENTATIVE

August 12, 2002 / 8:30 am
DATE/TIME

**Evaluation Ranking Criteria and Ranking Score
For Reserve and Onsite Pit Liner Requirements**

<u>Site-Specific Factors</u>	<u>Ranking</u>	<u>Site Ranking</u>
Distance to Groundwater (feet)		
>200	0	
100 to 200	5	
75 to 100	10	
25 to 75	15	
<25 or recharge area	20	<u>0</u>
Distance to Surf. Water (feet)		
>1000	0	
300 to 1000	2	
200 to 300	10	
100 to 200	15	
< 100	20	<u>10</u>
Distance to Nearest Municipal Well (feet)		
>5280	0	
1320 to 5280	5	
500 to 1320	10	
<500	20	<u>0</u>
Distance to Other Wells (feet)		
>1320	0	
300 to 1320	10	
<300	20	<u>0</u>
Native Soil Type		
Low permeability	0	
Mod. permeability	10	
High permeability	20	<u>10</u>
Fluid Type		
Air/mist	0	
Fresh Water	5	
TDS >5000 and <10000	10	
TDS >10000 or Oil Base Mud Fluid	15	
containing significant levels of hazardous constituents	20	<u>0</u>
Drill Cuttings		
Normal Rock	0	
Salt or detrimental	10	<u>0</u>
Annual Precipitation (inches)		
<10	0	
10 to 20	5	
>20	10	<u>5</u>
Affected Populations		
<10	0	
10 to 30	6	
30 to 50	8	
>50	10	<u>0</u>
Presence of Nearby Utility Conduits		
Not Present	0	
Unknown	10	
Present	15	<u>0</u>

Final Score 25 (Level I Sensitivity)


Sensitivity Level I = 20 or more; total containment is required.


Sensitivity Level II = 15-19; lining is discretionary.

Sensitivity Level III = below 15; no specific lining is required.

PLOT OF AN AREA WITH A RADIUS OF 5280 FEET FROM A POINT
N 1803 FEET, E 2148 FEET OF THE SW CORNER,
SECTION 29 TOWNSHIP 14S RANGE 10E SL BASE AND MERIDIAN

N O R T H





UTAH DIVISION OF WATER RIGHTS
NWPLAT POINT OF DIVERSION LOCATION PROGRAM

MAP CHAR	WATER RIGHT	QUANTITY CFS AND/OR	AC-FT	SOURCE DESCRIPTION or WELL INFO DIAMETER	DEPTH	YEAR LOG	POINT OF DIVERSION DESCRIPTION NORTH	EAST	CNR	SEC	TWN	RNG	B&
0	91 2295	.0000	.00	Price River									
		WATER USE(S): STOCKWATERING											PRIORITY DATE: 00/00/1
		Grosso, Severina											
0	91 2295	.0000	.00	Price River									
		WATER USE(S): STOCKWATERING											PRIORITY DATE: 00/00/1
		Grosso, Severina											
1	91 2297	.0000	.00	Price River									

		WATER USE(S): STOCKWATERING							PRIORITY DATE: 00/00/1
		Jewkes, Thelma M.		143 South 1st East					Price
1	91 2297	.0000	.00	Price River					
		WATER USE(S): STOCKWATERING							PRIORITY DATE: 00/00/1
		Jewkes, Thelma M.		143 South 1st East					Price
2	91 4977	.0000	4.37	Surface Runoff	S 1550	E 1300	N4 29	14S 10E S	
		WATER USE(S): IRRIGATION							PRIORITY DATE: 06/27/1
		Liddell, Blake		1398 South Fairgrounds Road					Price
3	91 3221	.0000	.00	Drunkards Wash					
		WATER USE(S): STOCKWATERING							PRIORITY DATE: 00/00/1
		Ruggeri, Sam							
4	91 3221	.0000	.00	Drunkards Wash					
		WATER USE(S): STOCKWATERING							PRIORITY DATE: 00/00/1
		Ruggeri, Sam							
5	91 3220	.0000	.00	Drunkards Wash					
		WATER USE(S): STOCKWATERING							PRIORITY DATE: 00/00/1
		Forrester, John C. & Patricia							
5	91 3220	.0000	.00	Drunkards Wash					
		WATER USE(S): STOCKWATERING							PRIORITY DATE: 00/00/1
		Forrester, John C. & Patricia							
6	91 3219	.0000	.00	Drunkards Wash					
		WATER USE(S): STOCKWATERING							PRIORITY DATE: 00/00/1
		Bonnell, Mildred		Route #3, Box 112-A					Price
		Waterman, Russell		Route #3, Box 112-A					Price
		Jensen, Alice		Route #3, Box 112-A					Price
		Randall, Beatrice		Route #3, Box 112-A					Price
		Hunt, Barbara		Route #3, Box 112-A					Price
		Williams, Betty Lou		Route #3, Box 112-A					Price
6	91 3219	.0000	.00	Drunkards Wash					
		WATER USE(S): STOCKWATERING							PRIORITY DATE: 00/00/1
		Bonnell, Mildred		Route #3, Box 112-A					Price
		Waterman, Russell		Route #3, Box 112-A					Price
		Jensen, Alice		Route #3, Box 112-A					Price
		Randall, Beatrice		Route #3, Box 112-A					Price
		Hunt, Barbara		Route #3, Box 112-A					Price
		Williams, Betty Lou		Route #3, Box 112-A					Price

<http://waterrights.utah.gov/cgi-bin/wwwplat.exe?rad=5280&ns=n1803&ew=e2148&cor=SW&sec=29&town=14S&range=10E...> 8/21/2002

<http://waterrights.utah.gov/cgi-bin/wwwplat.exe?rad=5280&ns=n1803&ew=e2148&cor=SW&sec=29&town=14S&range=10E...> 8/21/2002

		WATER USE(S): STOCKWATERING								PRIORITY DATE: 00/00/1
		Wells, William H. & Ella May								Ogden
J	91	3237	.0000	.00	Lone Tree Wash					
		WATER USE(S): STOCKWATERING								PRIORITY DATE: 00/00/1
		Robertson, Leland C.								Price
J	91	3237	.0000	.00	Lone Tree Wash					
		WATER USE(S): STOCKWATERING								PRIORITY DATE: 00/00/1
		Robertson, Leland C.								Price
K	91	258	3.6000	.00	Lone Tree Wash	S	2280	E	15	N4 32 14S 10E S
		WATER USE(S): IRRIGATION								PRIORITY DATE: 01/27/1
		LDS Church, Carbon Stake								
K	91	647	3.6000	.00	Lone Tree Wash	S	2280	E	15	N4 32 14S 10E S
		WATER USE(S): IRRIGATION STOCKWATERING								PRIORITY DATE: 01/27/1
		Himonas, George			222 North 1280 West					Price
		Himonas, Mike			222 North 1280 West					Price
		Himonas, Gust			222 North 1280 West					Price
K	91	651	3.6000	.00	Lone Tree Wash	S	2280	E	15	N4 32 14S 10E S
		WATER USE(S): IRRIGATION STOCKWATERING								PRIORITY DATE: 01/27/1
		Slaughter, Harold & Ione			Route #1					Price
L	91	4824	.0000	1.39	Lone Tree Wash	S	95	E	2256	W4 32 14S 10E S
		WATER USE(S): IRRIGATION STOCKWATERING								PRIORITY DATE: 06/09/1
		Scow, Gary W. & Mary D.			2565 South 660 West					Price
M	91	3236	.0000	.00	Lone Tree Wash					
		WATER USE(S): STOCKWATERING								PRIORITY DATE: 00/00/1
		Frandsen, R. H. & Lapriel			225 North 2nd East					Price
M	91	3236	.0000	.00	Lone Tree Wash					
		WATER USE(S): STOCKWATERING								PRIORITY DATE: 00/00/1
		Frandsen, R. H. & Lapriel			225 North 2nd East					Price



State of Utah

DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

1594 West North Temple, Suite 1210

PO Box 145801

Salt Lake City, Utah 84114-5801

(801) 538-5340 telephone

(801) 359-3940 fax

(801) 538-7223 TTY

www.nr.utah.gov

Michael O. Leavitt
Governor

Robert L. Morgan
Executive Director

Lowell P. Braxton
Division Director

September 4, 2002

Phillips Petroleum Company
P O Box 851
Price, UT 84501

Re: Schmidt 29-531 Well, 1803' FSL, 2148' FWL, NE SW, Sec. 29, T. 14 South, R. 10 East,
Carbon County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-007-30863.

Sincerely,

John R. Baza
Associate Director

pb
Enclosures
cc: Carbon County Assessor

Operator: Phillips Petroleum Company
Well Name & Number Schmidt 29-531
API Number: 43-007-30863
Lease: Fee

Location: NE SW Sec. 29 T. 14 South R. 10 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- 24 hours prior to cementing or testing casing
- 24 hours prior to testing blowout prevention equipment
- 24 hours prior to spudding the well
- within 24 hours of any emergency changes made to the approved drilling program
- prior to commencing operations to plug and abandon the well

The following are Division of Oil, Gas and Mining contacts and their work telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at (801) 538-5338
- Carol Daniels at (801) 538-5284 (spud)

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)



Re: Notice of Address Change, Merger and Name Change
Address Change effective **December 2, 2002**
Merger and Name Change effective **December 31, 2002**

Divisions of Oil, Gas, and Mining
Attn: Mr. John Baza
1594 West North Temple,
Suite 1210, P. O. Box 145801
Salt Lake City, UT 84114-5801

Gentlemen:

1. Effective December 2, 2002, Phillips Petroleum Company will close its Englewood, Colorado Rocky Mountain Region office. After that time, all correspondence, notices and invoice for Land related matters should be directed to the address(es) noted below. Note that until December 31, 2002, all properties in which Phillips held an interest will continue to be operated by Phillips Petroleum Company, a wholly-owned subsidiary of ConocoPhillips.

2. On December 31, 2002, Phillips Petroleum Company and Conoco Inc. will merge, and the surviving corporation will be renamed "ConocoPhillips Company".

In accordance with the notice provisions of the Operating Agreements and other agreements, if any, between our companies, please adjust your company/organization records, effective for address purposes as of December 2, 2002, and for company name purposes, as of January 1, 2003, to reflect the following information for addressing and delivery of notices, invoicing and payment, and communications with ConocoPhillips Company. This will also apply to Lease Sale notices and other lease-related correspondence and notifications.

U.S. Mail Address:

ConocoPhillips Company
P.O. Box 2197
Houston, Texas 77252
Attn: Chief Landman,
San Juan/Rockies

Physical Address & Overnight Delivery:

ConocoPhillips Company
550 Westlake Park Blvd.
Three Westlake Park
3WL, Room WL 9000
Houston, Texas 77079
Attn: Chief Landman,
San Juan/Rockies

All ballots and official notices/responses sent by facsimile transmission should be sent to the following contact:

Attn: Chief Landman,
San Juan/Rockies

Fax No.: 832-486-2688 or
832-486-2687

Please contact the undersigned immediately if you have any questions. This notice does not apply to royalty inquiries, joint interest billings, or revenue remittances. Please continue to use the same addresses you are currently using for these matters

Sincerely,

RECEIVED

DEC 02 2002

DIVISION OF
OIL, GAS AND MINING

OPERATOR CHANGE WORKSHEET

ROUTING

1. GLH

2. CDW

3. FILE

Change of Operator (Well Sold)

Designation of Agent/Operator

Operator Name Change

X MergerThe operator of the well(s) listed below has changed, effective: **12-31-02**

FROM: (Old Operator):	TO: (New Operator):
PHILLIPS PETROLEUM COMPANY	CONOCOPHILLIPS COMPANY
Address: 980 PLAZA OFFICE	Address: P O BOX 2197, WL3 4066
BARTLESVILLE, OK 74004	HOUSTON, TX 77252
Phone: 1-(918)-661-4415	Phone: 1-(832)-486-2329
Account No. N1475	Account No. N2335

CA No.

Unit:

WELL(S)

NAME	SEC TWN RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
SEELY 15-498	15-14S-08E	43-007-30797	99999	FEE	GW	APD
SEELY 15-499	15-14S-08E	43-007-30798	99999	FEE	GW	APD
SEELY 15-500	15-14S-08E	43-007-30799	99999	FEE	GW	APD
SEELY 22-501	22-14S-08E	43-007-30800	13667	FEE	GW	P
SEELY 22-492	22-14S-08E	43-007-30796	99999	FEE	GW	APD
SEELY 22-502	22-14S-08E	43-007-30801	99999	FEE	GW	APD
SEELY 22-503	22-14S-08E	43-007-30802	99999	FEE	GW	APD
USA 01-402	01-14S-09E	43-007-30629	13669	FEDERAL	GW	P
USA 01-504	01-14S-09E	43-007-30846	99999	FEDERAL	GW	NEW
USA 06-437	06-14S-09E	43-007-30831	13576	FEDERAL	GW	P
USA 06-488	06-14S-09E	43-007-30832	13668	FEDERAL	GW	P
USA 06-489	06-14S-09E	43-007-30833	13603	FEDERAL	GW	P
USA 12-536	12-14S-09E	43-007-30841	13670	FEDERAL	GW	P
USA 12-537	12-14S-09E	43-007-30842	13689	FEDERAL	GW	DRL
USA 12-538	12-14S-09E	43-007-30843	13690	FEDERAL	GW	DRL
USA 34-518	34-14S-09E	43-007-30803	99999	FEDERAL	GW	APD
UTAH 19-533	19-14S-10E	43-007-30891	99999	STATE	GW	APD
SCHMIDT 29-531	29-14S-10E	43-007-30863	99999	FEE	GW	APD
MCKENDRICK 29-548	29-14S-10E	43-007-30864	99999	FEE	GW	APD
COTNER 29-549	29-14S-10E	43-007-30865	99999	FEE	GW	APD

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 01/08/2003
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 01/08/2003
3. The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 02/03/2003
4. Is the new operator registered in the State of Utah: YES Business Number: 562960-0143
5. If **NO**, the operator was contacted on: _____

6. (R649-9-2)Waste Management Plan has been received on: IN PLACE

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: 01/14/2003

8. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: 01/14/2003

9. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: 01/14/2003

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 02/12/2003

2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 02/12/2003

3. Bond information entered in RBDMS on: N/A

4. Fee wells attached to bond in RBDMS on: N/A

STATE WELL(S) BOND VERIFICATION:

1. State well(s) covered by Bond Number: 8140-60-24

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: 8015-16-69

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: N/A

FEE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number 6196922

2. The **FORMER** operator has requested a release of liability from their bond on: N/A
The Division sent response by letter on: N/A

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: N/A

COMMENTS:



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Eastern States Office
7450 Boston Boulevard
Springfield, Virginia 22153

IN REPLY REFER TO
3106.8(932.34)WF

January 16, 2003

NOTICE

ConocoPhillips Company	:	Oil & Gas Leases
P.O. Box 7500	:	
Bartlesville, Oklahoma 74005	:	

Merger/Name Change Recognized

Acceptable evidence was received in this office on January 14, 2003, concerning the change of name of Phillips Petroleum Company to **ConocoPhillips Company** and the merger of **Conoco Incorporated** into **ConocoPhillips Company** on Federal oil and gas leases, with **ConocoPhillips Company** being the surviving entity.

The Secretary of the State of Delaware certified the effective date of this merger effective December 31, 2002.

The oil and gas lease files identified on the enclosed exhibit have been noted to the merger. The exhibit was compiled from a list of leases obtained from your list of leases. Eastern States has not abstracted the lease files to determine if the entities affected by this merger hold an interest in the leases identified nor have we attempted to identify leases where the entities are the operator on the ground maintaining no vested record title or operating rights interest. We are notifying the Minerals Management Service and all applicable Bureau of Land Management offices of this merger and name change by a copy of this notice. If additional documentation for changes of operator are required by our Field Offices, you will be contacted by them.

If you identify other leases in which the merging entity maintain an interest, please contact this office and we will appropriately document those files with a copy of this Notice.

By Operation of law the name of the principal on Nationwide Oil and Gas Bond held by Conoco Incorporated (ES0085) has been changed to ConocoPhillips Company.

If you have any questions, please contact Bill Forbes at 703-440-1536.

S/ Wilbert B. Forbes

Wilbert B. Forbes
Land Law Examiner
Branch of Use Authorization
Division of Resources Planning, Use
and Protection

bc: JFO, BLM State Offices, MMS, ES RF, 930 RF, ES-932:
Bforbes:wbf:01/16/03:440-1536/ConocoPhillips Co

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>All</u>		5. LEASE DESIGNATION AND SERIAL NUMBER:
2. NAME OF OPERATOR: Phillips Petroleum Company		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 980 Plaza Office CITY Bartlesville STATE OK ZIP 74004		7. UNIT or CA AGREEMENT NAME:
PHONE NUMBER: (918) 661-4415		8. WELL NAME and NUMBER: See Attached List
10. FIELD AND POOL, OR WILDCAT:		9. API NUMBER: See List

4. LOCATION OF WELL FOOTAGES AT SURFACE: See Attached List	COUNTY:
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:	STATE: UTAH


11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.


Conoco Inc. was merged into Phillips Petroleum Company, the surviving corporation, on December 31, 2002. In connection with this merger and effective on the same date, the name of the surviving corporation was changed to "ConocoPhillips Company". We are requesting that a new Operator Number be assigned to ConocoPhillips Company.

Please send production reporting forms to Herb Henderson at ConocoPhillips Company, 315 S. Johnstone, 980 Plaza Office, Bartlesville, OK 74004. Herb's phone number is 918-661-4415.

Current Operator
Phillips Petroleum Company


Steve de Albuquerque

New Operator
ConocoPhillips Company


Yolanda Perez

RECEIVED

JAN 08 2003

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) <u>Yolanda Perez</u>	TITLE <u>Sr. Regulatory Analyst</u>
SIGNATURE <u>Yolanda Perez</u>	DATE <u>12/30/2002</u>

(This space for State use only)




SECRETARY'S CERTIFICATE

I, the undersigned, Jennifer M. Garcia, Assistant Secretary of ConocoPhillips Company, formerly Phillips Petroleum Company, organized and existing under and by virtue of the laws of the State of Delaware (the "Corporation"), hereby certify that:

1. As Assistant Secretary I am authorized to execute this certificate on behalf of the Corporation.
2. The attached photocopy of the Certificate of Amendment to the Restated Certificate of Incorporation of Phillips Petroleum Company (to be renamed ConocoPhillips Company) is a true and correct copy as filed in the office of the Secretary of State of Delaware on the 12th day of December 2002, with an effective date of January 1, 2003 and such Certificate of Amendment has not been modified, amended, rescinded or revoked and is in full force and effect as of the date hereof.
3. The attached photocopy of the Certificate of Merger of Conoco Inc. with and into ConocoPhillips Company is a true and correct copy as filed in the office of the Secretary of State of Delaware on the 12th day of December 2002, with an effective date of December 31, 2002 and such Certificate of Merger has not been modified, amended, rescinded or revoked and is in full force and effect as of the date hereof.

IN WITNESS WHEREOF, I have hereunto set my hand as Assistant Secretary and affixed the corporate seal of the Corporation this 7th day of January 2003.


Assistant Secretary
ConocoPhillips Company


STATE OF TEXAS §
 §
COUNTY OF HARRIS §

This instrument was acknowledged before me on January 7, 2003, by Jennifer M. Garcia, Assistant Secretary of ConocoPhillips Company, a Delaware corporation, on behalf of said Corporation.



RECEIVED
JAN 08 2003

DIV. OF OIL, GAS & MINING


Notary Public

Delaware

PAGE 1

The First State


I, HARRIET SMITH WINDSOR, SECRETARY OF STATE OF THE STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND CORRECT COPY OF THE CERTIFICATE OF AMENDMENT OF "PHILLIPS PETROLEUM COMPANY", CHANGING ITS NAME FROM "PHILLIPS PETROLEUM COMPANY" TO "CONOCOPHILLIPS COMPANY", FILED IN THIS OFFICE ON THE TWELFTH DAY OF DECEMBER, A.D. 2002, AT 1:41 O'CLOCK P.M.

AND I DO HEREBY FURTHER CERTIFY THAT THE EFFECTIVE DATE OF THE AFORESAID CERTIFICATE OF AMENDMENT IS THE THIRTY-FIRST DAY OF DECEMBER, A.D. 2002, AT 11 O'CLOCK P.M.

RECEIVED

JAN 08 2003

DIV. OF OIL, GAS & MINING



0064324 8100

030002793

Harriet Smith Windsor

Harriet Smith Windsor, Secretary of State

AUTHENTICATION: 2183360

DATE: 01-02-03

CERTIFICATE OF AMENDMENT

to the

RESTATED CERTIFICATE OF INCORPORATION

of

**PHILLIPS PETROLEUM COMPANY
(to be renamed ConocoPhillips Company)**

Phillips Petroleum Company ("Phillips"), a corporation organized and existing under the General Corporation Law of the State of Delaware (the "DGCL"), hereby certifies that:

1. The amendments to Phillips' Restated Certificate of Incorporation set forth below were duly adopted in accordance with the provisions of Section 242 of the DGCL and have been consented to in writing by the sole stockholder of Phillips in accordance with Section 228 of the DGCL.

2. Phillips' Restated Certificate of Incorporation is hereby amended by deleting Article I thereof and replacing in lieu thereof a new Article I reading in its entirety as follows:

"The name of the corporation (which is hereinafter referred to as the "Corporation") is ConocoPhillips Company."

3. Phillips' Restated Certificate of Incorporation is hereby amended by deleting Section 1 of Article IV thereof and replacing in lieu thereof a new Section 1 reading in its entirety as follows:

"Section 1. The Corporation shall be authorized to issue 2,100 shares of capital stock, of which 2,100 shares shall be shares of Common Stock, \$.01 par value ("Common Stock")."

4. Pursuant to Section 103(d) of the DGCL, this amendment will become effective at 11:00 p.m., Eastern time, on December 31, 2002.

FROM RL&F#1

(THU) 12.12'02 13:32/ST. 13:31/NO. 4864756279 P 6

IN WITNESS WHEREOF, Phillips has caused this certificate to be executed this
12th day of December, 2002.

PHILLIPS PETROLEUM COMPANY

W7

By: _____

Name: Rick A. Harrington

Title: Senior Vice President, Legal,
and General Counsel

HQU03:884504.1

RECEIVED
JAN 08 2003
DIV. OF OIL, GAS & MINING

Delaware

PAGE 1

The First State

I, HARRIET SMITH WINDSOR, SECRETARY OF STATE OF THE STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND CORRECT COPY OF THE CERTIFICATE OF MERGER, WHICH MERGES:

"CONOCO INC.", A DELAWARE CORPORATION,


WITH AND INTO "CONOCOPHILLIPS COMPANY" UNDER THE NAME OF "CONOCOPHILLIPS COMPANY", A CORPORATION ORGANIZED AND EXISTING UNDER THE LAWS OF THE STATE OF DELAWARE, AS RECEIVED AND FILED IN THIS OFFICE THE TWELFTH DAY OF DECEMBER, A.D. 2002, AT 1:44 O'CLOCK P.M.

AND I DO HEREBY FURTHER CERTIFY THAT THE EFFECTIVE DATE OF THE AFORESAID CERTIFICATE OF MERGER IS THE THIRTY-FIRST DAY OF DECEMBER, A.D. 2002, AT 11:59 O'CLOCK P.M.

RECEIVED

JAN 08 2003

DIV. OF OIL, GAS & MINING



0064324 8100M

030002793

Harriet Smith Windsor

Harriet Smith Windsor, Secretary of State

AUTHENTICATION: 2183370

DATE: 01-02-03

CERTIFICATE OF MERGER

of

Conoco Inc.
(a Delaware corporation)

with and into

ConocoPhillips Company
(a Delaware corporation)

Phillips Petroleum Company, a Delaware corporation to be renamed ConocoPhillips Company prior to the effective time of this certificate of merger (the "Surviving Corporation"), in compliance with the requirements of the General Corporation Law of the State of Delaware (the "DGCL") and desiring to effect a merger of Conoco Inc., a Delaware corporation formerly incorporated under the name Du Pont Holdings, Inc. (the "Merging Corporation" and together with the Surviving Corporation, the "Constituent Corporations"), with and into the Surviving Corporation, and acting by its duly authorized officer, DOES HEREBY CERTIFY that:

First: As of the date hereof, the name and state of incorporation of each of the Constituent Corporations of the merger are as follows:

<u>NAME</u>	<u>STATE OF INCORPORATION</u>
PHILLIPS PETROLEUM COMPANY	Delaware
CONOCO INC.	Delaware

Second: An agreement and plan of merger has been approved, adopted, certified, executed and acknowledged by each of the Constituent Corporations in accordance with the requirements of Section 251 of the DGCL;

Third: The name of the Surviving Corporation will be ConocoPhillips Company;

Fourth: The Certificate of Incorporation of ConocoPhillips Company immediately prior to the merger shall be the Certificate of Incorporation of the Surviving Corporation until such time as it may be amended in accordance with applicable law and the provisions thereof;

Fifth: The executed agreement and plan of merger is on file at an office of the Surviving Corporation, the address of which is 600 North Dairy Ashford, Houston, Texas 77079;

RECEIVED

JAN 08 2003


DIV. OF OIL, GAS & MINING

Sixth: A copy of the agreement and plan of merger will be furnished by the Surviving Corporation, on request and without cost, to any stockholder of any Constituent Corporation; and

Seventh: Pursuant to Section 103(d) of the DGCL, this certificate of merger will become effective at 11:59 p.m., Eastern time, on December 31, 2002.

Dated: December 12, 2002

PHILLIPS PETROLEUM COMPANY
(a Delaware corporation)

By: 
Name: Rick A. Harrington
Title: Senior Vice President, Legal,
and General Counsel

STATE OF UTAH
DEPARTMENT OF COMMERCE
REGISTRATION

CONOCOPHILLIPS COMPANY

EFFECTIVE
06/14/1946

EXPIRATION
*RENEWAL

REFERENCE NUMBER(S), CLASSIFICATION(S) & DETAIL(S)

Corporation - Foreign - Profit
562960-0143

UNITED STATES CORP CO
CONOCOPHILLIPS COMPANY
GATEWAY TOWER EAST STE 900
10 EAST SOUTH TEMPLE
SLC UT 84133

RECEIVED

JAN 08 2003

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF COMMERCE
DIVISION OF CORPORATIONS & COMMERCIAL CODE
REGISTRATION

EFFECTIVE DATE: 06/14/1946
EXPIRATION DATE: *RENEWAL
ISSUED TO: CONOCOPHILLIPS COMPANY



REFERENCE NUMBER(S), CLASSIFICATION(S) & DETAIL(S)
562960-0143 Corporation - Foreign - Profit
*RENEWAL

You will need to renew your registration each anniversary date of the effective date.
Exceptions: DBAs and Business Trusts renew every three (3) years from the effective date.

Utah Well List as of 12/26/02

API Well Number	Well Name	Well Type	Well Status	Sec	Twpn	Twpd	Rngn	Rngd
43-007-30887-00-00	ANDREEN 32-529	Gas Well	APD	32	14	S	10	E
43-007-30865-00-00	COTNER 29-549	Gas Well	APD	29	14	S	10	E
43-007-30837-00-00	DALLIN 32-615	Gas Well	APD	32	13	S	9	E
43-047-34551-00-00	FED 43-24-3 #1	Gas Well	APD	24	10	S	17	E
43-047-33982-00-00	FEDERAL 12-17 #1	Gas Well	APD	17	10	S	18	E
43-047-34471-00-00	FEDERAL 12-29-7 1	Gas Well	APD	29	9	S	19	E
43-047-34472-00-00	FEDERAL 31-31-6 1	Gas Well	APD	31	9	S	19	E
43-007-30864-00-00	MCKENDRICK 29-548	Gas Well	APD	29	14	S	10	E
43-015-30512-00-00	PPCO 19-379	Gas Well	APD	19	16	S	9	E
43-015-30515-00-00	PPCO 24-562	Gas Well	APD	24	16	S	8	E
43-015-30548-00-00	PPCO 30-605	Gas Well	APD	30	16	S	9	E
43-007-30888-00-00	PRICE 32-438	Gas Well	APD	32	14	S	10	E
43-007-30813-00-00	RITZAKIS 33-514	Gas Well	APD	33	13	S	9	E
43-007-30766-00-00	RITZAKIS 33-516	Gas Well	APD	33	13	S	9	E
43-007-30838-00-00	ROWLEY 32-616	Gas Well	APD	32	13	S	9	E
43-007-30863-00-00	SCHMIDT 29-531	Gas Well	APD	29	14	S	10	E
43-007-30797-00-00	SEELY 15-498	Gas Well	APD	15	14	S	8	E
43-007-30798-00-00	SEELY 15-499	Gas Well	APD	15	14	S	8	E
43-007-30799-00-00	SEELY 15-500	Gas Well	APD	15	14	S	8	E
43-007-30796-00-00	SEELY 22-492	Gas Well	APD	22	14	S	8	E
43-007-30801-00-00	SEELY 22-502	Gas Well	APD	22	14	S	8	E
43-007-30802-00-00	SEELY 22-503	Gas Well	APD	22	14	S	8	E
43-007-30711-00-00	USA 09-452	Gas Well	APD	9	15	S	8	E
43-015-30351-00-00	USA 11-313	Gas Well	APD	11	16	S	9	E
43-015-30398-00-00	USA 12-385	Gas Well	APD	12	16	S	9	E
43-015-30409-00-00	USA 12-426	Gas Well	APD	12	16	S	9	E
43-007-30805-00-00	USA 14-490	Gas Well	APD	14	14	S	8	E
43-007-30806-00-00	USA 14-491	Gas Well	APD	14	14	S	8	E
43-007-30676-00-00	USA 15-421	Gas Well	APD	15	15	S	8	E
43-015-30417-00-00	USA 21-427	Gas Well	APD	21	16	S	9	E
43-015-30416-00-00	USA 21-428	Gas Well	APD	21	16	S	9	E
43-015-30415-00-00	USA 21-429	Gas Well	APD	21	16	S	9	E
43-007-30515-00-00	USA 31-309	Gas Well	APD	31	15	S	10	E
43-007-30835-00-00	USA 33-515	Gas Well	APD	33	13	S	9	E
43-007-30836-00-00	USA 33-624	Gas Well	APD	33	13	S	9	E
43-007-30803-00-00	USA 34-518	Gas Well	APD	34	14	S	8	E
43-007-30478-00-00	UTAH 05-224	Gas Well	APD	5	15	S	9	E
43-015-30411-00-00	UTAH 16-365	Gas Well	APD	16	16	S	9	E
43-015-30412-00-00	UTAH 16-366	Gas Well	APD	16	16	S	9	E
43-015-30413-00-00	UTAH 16-430	Gas Well	APD	16	16	S	9	E
43-015-30299-00-00	UTAH 18-374	Gas Well	APD	18	16	S	9	E
43-015-30420-00-00	UTAH 19-377	Gas Well	APD	19	16	S	9	E
43-015-30492-00-00	UTAH 19-378	Gas Well	APD	19	16	S	9	E
43-007-30891-00-00	UTAH 19-533	Gas Well	APD	19	14	S	10	E
43-015-30414-00-00	UTAH 20-381	Gas Well	APD	20	16	S	9	E
43-015-30421-00-00	UTAH 20-382	Gas Well	APD	20	16	S	9	E
43-015-30518-00-00	UTAH 25-576	Gas Well	APD	25	16	S	8	E
43-015-30539-00-00	UTAH 25-578	Gas Well	APD	25	16	S	8	E
43-015-30540-00-00	UTAH 25-579	Gas Well	APD	25	16	S	8	E
43-007-30817-00-00	UTAH 25-618	Gas Well	APD	25	13	S	9	E
43-015-30543-00-00	UTAH 26-582	Gas Well	APD	26	16	S	8	E
43-015-30547-00-00	UTAH 29-608	Gas Well	APD	29	16	S	9	E
43-007-30889-00-00	UTAH 32-128	Gas Well	APD	32	14	S	10	E
43-007-30814-00-00	UTAH 35-506	Gas Well	APD	35	13	S	9	E

Utah Well List as of 12/26/02

API Well Number	Well Name	Well Type	Well Status	Sec	Twpn	Twpd	Rngn	Rngd
43-047-33750-00-00	FEDERAL 34-29	Gas Well	P	29	9	S	19	E
43-007-30782-00-00	GAROFOLA 26-482	Gas Well	P	26	15	S	8	E
43-007-30335-00-00	GIACOLETTO 11-113	Gas Well	P	11	14	S	9	E
43-007-30407-00-00	GIACOLETTO 13-120	Gas Well	P	13	14	S	9	E
43-007-30345-00-00	GIACOLETTO 14-121	Gas Well	P	14	14	S	9	E
43-007-30487-00-00	HELPER & ASSOC 07-307	Gas Well	P	7	15	S	9	E
43-007-30459-00-00	HELPER & ASSOC 18-236	Gas Well	P	18	15	S	9	E
43-007-30720-00-00	HELPER & ASSOC 18-308	Gas Well	P	18	15	S	9	E
43-007-30412-00-00	HELPER & ASSOC 8-232	Gas Well	P	8	15	S	9	E
43-007-30258-00-00	HELPER & ASSOCIATES 7-84	Gas Well	P	7	15	S	9	E
43-007-30588-00-00	JENSEN 16-132	Gas Well	P	16	15	S	10	E
43-007-30420-00-00	KAKATSIDES 31-197	Gas Well	P	31	14	S	9	E
43-007-30296-00-00	LDS 17-133	Gas Well	P	17	15	S	10	E
43-007-30323-00-00	PAAR 16-146	Gas Well	P	16	14	S	9	E
43-047-34286-00-00	PETES WASH 23-12 #1	Gas Well	P	12	10	S	17	E
43-007-30748-00-00	PIERUCCI 25-461	Gas Well	P	25	15	S	8	E
43-007-30749-00-00	PIERUCCI 25-462	Gas Well	P	25	15	S	8	E
43-007-30754-00-00	PIERUCCI 26-463	Gas Well	P	26	15	S	8	E
43-007-30755-00-00	PIERUCCI 26-464	Gas Well	P	26	15	S	8	E
43-007-30745-00-00	PIERUCCI 26-481	Gas Well	P	26	15	S	8	E
43-007-30117-00-00	PINNACLE PEAK 19-171	Gas Well	P	19	14	S	9	E
43-007-30845-00-00	PMC 10-526	Gas Well	P	10	15	S	8	E
43-007-30282-00-00	POWELL 19-104	Gas Well	P	19	15	S	10	E
43-007-30283-00-00	POWELL 19-105	Gas Well	P	19	15	S	10	E
43-007-30346-00-00	POWELL 30-173	Gas Well	P	30	15	S	10	E
43-015-30279-00-00	PPCO 10-557	Gas Well	P	10	16	S	8	E
43-015-30494-00-00	PPCO 15-555	Gas Well	P	15	16	S	8	E
43-007-30211-00-00	PRETTYMAN 10-15-34	Gas Well	P	10	14	S	9	E
43-007-30340-00-00	PRETTYMAN 11-114	Gas Well	P	11	14	S	9	E
43-007-30653-00-00	RGC 21-331	Gas Well	P	21	15	S	9	E
43-007-30743-00-00	RGC 21-332	Gas Well	P	21	15	S	9	E
43-007-30747-00-00	RGC 25-460	Gas Well	P	25	15	S	8	E
43-007-30559-00-00	RGC 28-318	Gas Well	P	28	15	S	9	E
43-007-30518-00-00	RGC 28-319	Gas Well	P	28	15	S	9	E
43-007-30509-00-00	RITZAKIS 03-408	Gas Well	P	3	14	S	9	E
43-007-30473-00-00	RITZAKIS 5-304	Gas Well	P	5	14	S	9	E
43-007-30474-00-00	RITZAKIS 5-305	Gas Well	P	5	14	S	9	E
43-007-30475-00-00	RITZAKIS 8-298	Gas Well	P	8	14	S	9	E
43-007-30479-00-00	RITZAKIS 8-299	Gas Well	P	8	14	S	9	E
43-007-30476-00-00	RITZAKIS 8-300	Gas Well	P	8	14	S	9	E
43-007-30374-00-00	ROBERTSON 32-127	Gas Well	P	32	14	S	10	E
43-007-30610-00-00	SAMPINOS 16-131	Gas Well	P	16	15	S	10	E
43-007-30723-00-00	SAMPINOS 16-454	Gas Well	P	16	15	S	10	E
43-007-30765-00-00	SAMPINOS 16-521	Gas Well	P	16	15	S	10	E
43-007-30800-00-00	SEELY 22-501	Gas Well	P	22	14	S	8	E
43-007-30130-00-00	ST OF UT 25-9-1	Gas Well	P	25	14	S	9	E
43-007-30142-00-00	ST OF UT 36-3-4	Gas Well	P	36	14	S	9	E
43-007-30116-00-00	STELLA-HAMAKER 10-174	Gas Well	P	10	15	S	8	E
43-007-30746-00-00	TABOR 23-468	Gas Well	P	23	15	S	8	E
43-007-30319-00-00	TELONIS 15-142	Gas Well	P	15	14	S	9	E
43-007-30322-00-00	TELONIS 16-145	Gas Well	P	16	14	S	9	E
43-007-30300-00-00	TELONIS 19-150	Gas Well	P	19	14	S	9	E
43-007-30299-00-00	TELONIS 19-151	Gas Well	P	19	14	S	9	E
43-007-30327-00-00	TELONIS 20-152	Gas Well	P	20	14	S	9	E

Utah Well List as of 12/26/02

API Well Number	Well Name	Well Type	Well Status	Sec	Twpr	Twpr	Rngn	Rngd
43-007-30631-00-00	USA 13-419	Gas Well	P	13	15	S	8	E
43-007-30707-00-00	USA 13-447	Gas Well	P	13	14	S	8	E
43-007-30706-00-00	USA 13-470	Gas Well	P	13	14	S	8	E
43-007-30789-00-00	USA 13-474	Gas Well	P	13	14	S	8	E
43-007-30790-00-00	USA 13-475	Gas Well	P	13	14	S	8	E
43-007-30568-00-00	USA 13-91	Gas Well	P	13	14	S	9	E
43-007-30404-00-00	USA 14-122	Gas Well	P	14	14	S	9	E
43-015-30418-00-00	USA 1-425	Gas Well	P	1	16	S	9	E
43-007-30579-00-00	USA 14-325	Gas Well	P	14	15	S	8	E
43-007-30634-00-00	USA 14-386	Gas Well	P	14	15	S	8	E
43-007-30646-00-00	USA 14-416	Gas Well	P	14	15	S	8	E
43-007-30647-00-00	USA 14-417	Gas Well	P	14	15	S	8	E
43-007-30791-00-00	USA 14-476	Gas Well	P	14	14	S	8	E
43-007-30792-00-00	USA 14-477	Gas Well	P	14	14	S	8	E
43-007-30529-00-00	USA 14-74	Gas Well	P	14	14	S	9	E
43-007-30263-00-00	USA 14-75	Gas Well	P	14	14	S	9	E
43-007-30450-00-00	USA 15-176	Gas Well	P	15	14	S	9	E
43-007-30423-00-00	USA 15-177	Gas Well	P	15	14	S	9	E
43-007-30690-00-00	USA 15-420	Gas Well	P	15	15	S	8	E
43-007-30691-00-00	USA 15-422	Gas Well	P	15	15	S	8	E
43-007-30264-00-00	USA 15-88	Gas Well	P	15	14	S	9	E
43-007-30422-00-00	USA 17-179	Gas Well	P	17	14	S	9	E
43-007-30622-00-00	USA 17-180A	Gas Well	P	17	14	S	9	E
43-007-30618-00-00	USA 18-181	Gas Well	P	18	14	S	9	E
43-007-30417-00-00	USA 18-182	Gas Well	P	18	14	S	9	E
43-007-30619-00-00	USA 18-435	Gas Well	P	18	14	S	9	E
43-007-30393-00-00	USA 19-222	Gas Well	P	19	15	S	10	E
43-007-30392-00-00	USA 19-73	Gas Well	P	19	15	S	10	E
43-007-30448-00-00	USA 20-287	Gas Well	P	20	15	S	10	E
43-007-30451-00-00	USA 20-288	Gas Well	P	20	15	S	10	E
43-007-30590-00-00	USA 20-398	Gas Well	P	20	15	S	10	E
43-007-30591-00-00	USA 20-399	Gas Well	P	20	15	S	10	E
43-007-30424-00-00	USA 21-184	Gas Well	P	21	14	S	9	E
43-007-30425-00-00	USA 21-35	Gas Well	P	21	14	S	9	E
43-007-30426-00-00	USA 22-185	Gas Well	P	22	14	S	9	E
43-007-30477-00-00	USA 22-186	Gas Well	P	22	14	S	9	E
43-007-30700-00-00	USA 22-466	Gas Well	P	22	15	S	8	E
43-007-30611-00-00	USA 23-423	Gas Well	P	23	14	S	8	E
43-007-30650-00-00	USA 23-445	Gas Well	P	23	15	S	8	E
43-007-30704-00-00	USA 23-451	Gas Well	P	23	15	S	8	E
43-007-30503-00-00	USA 23-467	Gas Well	P	23	15	S	8	E
43-007-30793-00-00	USA 23-478	Gas Well	P	23	14	S	8	E
43-007-30794-00-00	USA 23-479	Gas Well	P	23	14	S	8	E
43-007-30795-00-00	USA 23-480	Gas Well	P	23	14	S	8	E
43-007-30469-00-00	USA 24-183	Gas Well	P	24	14	S	8	E
43-007-30612-00-00	USA 24-387	Gas Well	P	24	14	S	8	E
43-007-30613-00-00	USA 24-388	Gas Well	P	24	14	S	8	E
43-007-30651-00-00	USA 24-443	Gas Well	P	24	15	S	8	E
43-007-30648-00-00	USA 24-444	Gas Well	P	24	15	S	8	E
43-007-30708-00-00	USA 24-446	Gas Well	P	24	14	S	8	E
43-007-30652-00-00	USA 24-448	Gas Well	P	24	15	S	8	E
43-007-30705-00-00	USA 24-449	Gas Well	P	24	15	S	8	E
43-007-30505-00-00	USA 25-459	Gas Well	P	25	15	S	8	E
43-007-30614-00-00	USA 26-393	Gas Well	P	26	14	S	8	E

Utah Well List as of 12/26/02

API Well Number	Well Name	Well Type	Well Status	Sec	Twpn	Twpd	Rngn	Rngd
43-007-30430-00-00	UTAH 06-223	Gas Well	P	6	15	S	9	E
43-007-30562-00-00	UTAH 06-330	Gas Well	P	6	15	S	9	E
43-007-30716-00-00	UTAH 06-483	Gas Well	P	6	15	S	9	E
43-007-30409-00-00	UTAH 07-234	Gas Well	P	7	15	S	9	E
43-007-30421-00-00	UTAH 07-235	Gas Well	P	7	15	S	9	E
43-007-30411-00-00	UTAH 08-231	Gas Well	P	8	15	S	9	E
43-007-30488-00-00	UTAH 08-233	Gas Well	P	8	15	S	9	E
43-015-30464-00-00	UTAH 08-354	Gas Well	P	8	16	S	9	E
43-015-30378-00-00	UTAH 08-355	Gas Well	P	8	16	S	9	E
43-015-30379-00-00	UTAH 08-356	Gas Well	P	8	16	S	9	E
43-015-30380-00-00	UTAH 08-357	Gas Well	P	8	16	S	9	E
43-007-30449-00-00	UTAH 09-227	Gas Well	P	9	15	S	9	E
43-007-30561-00-00	UTAH 09-329	Gas Well	P	9	15	S	9	E
43-015-30300-00-00	UTAH 09-358	Gas Well	P	9	16	S	9	E
43-015-30407-00-00	UTAH 09-359	Gas Well	P	9	16	S	9	E
43-015-30397-00-00	UTAH 09-360	Gas Well	P	9	16	S	9	E
43-015-30408-00-00	UTAH 09-361	Gas Well	P	9	16	S	9	E
43-007-30580-00-00	UTAH 09-412	Gas Well	P	9	15	S	10	E
43-007-30605-00-00	UTAH 09-413	Gas Well	P	9	15	S	10	E
43-007-30657-00-00	UTAH 09-450	Gas Well	P	9	15	S	10	E
43-007-30722-00-00	UTAH 09-453	Gas Well	P	9	15	S	10	E
43-007-30302-00-00	UTAH 10-01-36	Gas Well	P	10	15	S	9	E
43-007-30298-00-00	UTAH 10-219	Gas Well	P	10	15	S	9	E
43-007-30432-00-00	UTAH 10-220	Gas Well	P	10	15	S	9	E
43-007-30303-00-00	UTAH 10-221	Gas Well	P	10	15	S	9	E
43-007-30228-00-00	UTAH 11-50	Gas Well	P	11	15	S	9	E
43-007-30229-00-00	UTAH 11-51	Gas Well	P	11	15	S	9	E
43-007-30230-00-00	UTAH 11-52	Gas Well	P	11	15	S	9	E
43-007-30231-00-00	UTAH 11-53	Gas Well	P	11	15	S	9	E
43-007-30467-00-00	UTAH 1-209	Gas Well	P	1	15	S	8	E
43-007-30210-00-00	UTAH 12-15-37	Gas Well	P	12	15	S	9	E
43-007-30232-00-00	UTAH 12-54	Gas Well	P	12	15	S	9	E
43-007-30233-00-00	UTAH 12-55	Gas Well	P	12	15	S	9	E
43-007-30234-00-00	UTAH 12-56	Gas Well	P	12	15	S	9	E
43-015-30493-00-00	UTAH 13-376	Gas Well	P	13	16	S	8	E
43-015-30301-00-00	UTAH 13-550	Gas Well	P	13	16	S	8	E
43-007-30243-00-00	UTAH 13-65	Gas Well	P	13	15	S	9	E
43-007-30244-00-00	UTAH 13-66	Gas Well	P	13	15	S	9	E
43-007-30245-00-00	UTAH 13-67	Gas Well	P	13	15	S	9	E
43-007-30246-00-00	UTAH 13-68	Gas Well	P	13	15	S	9	E
43-007-30439-00-00	UTAH 13-92	Gas Well	P	13	14	S	9	E
43-007-30220-00-00	UTAH 1-42	Gas Well	P	1	15	S	9	E
43-007-30221-00-00	UTAH 1-43	Gas Well	P	1	15	S	9	E
43-007-30222-00-00	UTAH 1-44	Gas Well	P	1	15	S	9	E
43-007-30223-00-00	UTAH 1-45	Gas Well	P	1	15	S	9	E
43-015-30330-00-00	UTAH 14-551	Gas Well	P	14	16	S	8	E
43-015-30331-00-00	UTAH 14-552	Gas Well	P	14	16	S	8	E
43-007-30239-00-00	UTAH 14-61	Gas Well	P	14	15	S	9	E
43-007-30240-00-00	UTAH 14-62	Gas Well	P	14	15	S	9	E
43-007-30241-00-00	UTAH 14-63	Gas Well	P	14	15	S	9	E
43-007-30242-00-00	UTAH 14-64	Gas Well	P	14	15	S	9	E
43-015-30334-00-00	UTAH 15-553	Gas Well	P	15	16	S	8	E
43-007-30416-00-00	UTAH 17-101	Gas Well	P	17	15	S	10	E
43-007-30277-00-00	UTAH 17-102	Gas Well	P	17	15	S	10	E

Utah Well List as of 12/26/02

API Well Number	Well Name	Well Type	Well Status	Sec	Twpn	Twpd	Rngn	Rngd
43-007-30255-00-00	UTAH 24-80	Gas Well	P	24	15	S	9	E
43-007-30256-00-00	UTAH 24-81	Gas Well	P	24	15	S	9	E
43-007-30267-00-00	UTAH 24-86	Gas Well	P	24	15	S	9	E
43-007-30375-00-00	UTAH 24-87	Gas Well	P	24	15	S	9	E
43-007-30227-00-00	UTAH 2-49	Gas Well	P	2	15	S	9	E
43-007-30157-00-00	UTAH 25-11-7	Gas Well	P	25	14	S	9	E
43-007-30399-00-00	UTAH 25-134	Gas Well	P	25	15	S	9	E
43-007-30400-00-00	UTAH 25-252	Gas Well	P	25	15	S	9	E
43-007-30401-00-00	UTAH 25-253	Gas Well	P	25	15	S	9	E
43-007-30402-00-00	UTAH 25-254	Gas Well	P	25	15	S	9	E
43-007-30600-00-00	UTAH 25-389	Gas Well	P	25	14	S	8	E
43-007-30599-00-00	UTAH 25-390	Gas Well	P	25	14	S	8	E
43-007-30658-00-00	UTAH 25-391	Gas Well	P	25	14	S	8	E
43-007-30602-00-00	UTAH 25-392	Gas Well	P	25	14	S	8	E
43-007-30206-00-00	UTAH 25-4-33	Gas Well	P	25	14	S	9	E
43-015-30519-00-00	UTAH 25-577	Gas Well	P	25	16	S	8	E
43-007-30156-00-00	UTAH 25-7-6	Gas Well	P	25	14	S	9	E
43-007-30204-00-00	UTAH 26-11-25	Gas Well	P	26	14	S	9	E
43-007-30205-00-00	UTAH 26-1-23	Gas Well	P	26	14	S	9	E
43-007-30181-00-00	UTAH 26-16-8	Gas Well	P	26	14	S	9	E
43-007-30446-00-00	UTAH 26-255	Gas Well	P	26	15	S	9	E
43-007-30445-00-00	UTAH 26-256	Gas Well	P	26	15	S	9	E
43-007-30444-00-00	UTAH 26-257	Gas Well	P	26	15	S	9	E
43-007-30514-00-00	UTAH 26-267	Gas Well	P	26	15	S	9	E
43-015-30541-00-00	UTAH 26-580	Gas Well	P	26	16	S	8	E
43-015-30542-00-00	UTAH 26-581	Gas Well	P	26	16	S	8	E
43-015-30544-00-00	UTAH 26-583	Gas Well	P	26	16	S	8	E
43-007-30202-00-00	UTAH 26-6-24	Gas Well	P	26	14	S	9	E
43-007-30395-00-00	UTAH 27-187	Gas Well	P	27	14	S	9	E
43-007-30292-00-00	UTAH 27-188	Gas Well	P	27	14	S	9	E
43-007-30457-00-00	UTAH 27-268	Gas Well	P	27	15	S	9	E
43-007-30458-00-00	UTAH 27-269	Gas Well	P	27	15	S	9	E
43-007-30712-00-00	UTAH 27-457	Gas Well	P	27	14	S	8	E
43-007-30714-00-00	UTAH 27-458	Gas Well	P	27	14	S	8	E
43-007-30777-00-00	UTAH 27-520	Gas Well	P	27	14	S	8	E
43-015-30545-00-00	UTAH 27-584	Gas Well	P	27	16	S	8	E
43-007-30193-00-00	UTAH 27-8-29	Gas Well	P	27	14	S	9	E
43-007-30186-00-00	UTAH 27-9-30	Gas Well	P	27	14	S	9	E
43-007-30396-00-00	UTAH 28-189	Gas Well	P	28	14	S	9	E
43-007-30397-00-00	UTAH 28-190	Gas Well	P	28	14	S	9	E
43-007-30293-00-00	UTAH 28-191	Gas Well	P	28	14	S	9	E
43-007-30294-00-00	UTAH 28-192	Gas Well	P	28	14	S	9	E
43-007-30551-00-00	UTAH 28-320	Gas Well	P	28	15	S	9	E
43-007-30560-00-00	UTAH 28-321	Gas Well	P	28	15	S	9	E
43-007-30405-00-00	UTAH 29-193	Gas Well	P	29	14	S	9	E
43-007-30427-00-00	UTAH 29-194	Gas Well	P	29	14	S	9	E
43-007-30739-00-00	UTAH 29-339	Gas Well	P	29	15	S	9	E
43-007-30740-00-00	UTAH 29-340	Gas Well	P	29	15	S	9	E
43-007-30741-00-00	UTAH 29-341	Gas Well	P	29	15	S	9	E
43-007-30742-00-00	UTAH 29-342	Gas Well	P	29	15	S	9	E
43-007-30262-00-00	UTAH 30-125	Gas Well	P	30	14	S	10	E
43-007-30185-00-00	UTAH 30-13-14	Gas Well	P	30	14	S	10	E
43-007-30265-00-00	UTAH 30-195	Gas Well	P	30	14	S	9	E
43-007-30344-00-00	UTAH 30-196	Gas Well	P	30	14	S	9	E

Utah Well List as of 12/26/02

API Well Number	Well Name	Well Type	Well Status	Sec	Twpn	Twpd	Rngn	Rngd
43-007-30178-00-00	UTAH 36-1-2	Gas Well	P	36	14	S	9	E
43-007-30341-00-00	UTAH 36-135	Gas Well	P	36	15	S	9	E
43-007-30343-00-00	UTAH 36-136	Gas Well	P	36	15	S	9	E
43-007-30342-00-00	UTAH 36-137	Gas Well	P	36	15	S	9	E
43-007-30315-00-00	UTAH 36-162	Gas Well	P	36	14	S	8	E
43-007-30316-00-00	UTAH 36-163	Gas Well	P	36	14	S	8	E
43-007-30317-00-00	UTAH 36-164	Gas Well	P	36	14	S	8	E
43-007-30318-00-00	UTAH 36-165	Gas Well	P	36	14	S	8	E
43-007-30144-00-00	UTAH 36-9-5	Gas Well	P	36	14	S	9	E
43-015-30341-00-00	UTAH 4-280	Gas Well	P	4	16	S	9	E
43-015-30342-00-00	UTAH 4-282	Gas Well	P	4	16	S	9	E
43-007-30384-00-00	UTAH 5-205	Gas Well	P	5	15	S	9	E
43-007-30269-00-00	UTAH 5-94	Gas Well	P	5	15	S	10	E
43-007-30270-00-00	UTAH 5-95	Gas Well	P	5	15	S	10	E
43-007-30271-00-00	UTAH 5-96	Gas Well	P	5	15	S	10	E
43-007-30217-00-00	UTAH 6-38	Gas Well	P	6	15	S	10	E
43-007-30218-00-00	UTAH 6-39	Gas Well	P	6	15	S	10	E
43-007-30219-00-00	UTAH 6-40	Gas Well	P	6	15	S	10	E
43-007-30254-00-00	UTAH 6-41	Gas Well	P	6	15	S	10	E
43-007-30235-00-00	UTAH 7-57	Gas Well	P	7	15	S	10	E
43-007-30236-00-00	UTAH 7-58	Gas Well	P	7	15	S	10	E
43-007-30237-00-00	UTAH 7-59	Gas Well	P	7	15	S	10	E
43-007-30238-00-00	UTAH 7-60	Gas Well	P	7	15	S	10	E
43-007-30275-00-00	UTAH 8-100	Gas Well	P	8	15	S	10	E
43-007-30410-00-00	UTAH 8-230	Gas Well	P	8	15	S	9	E
43-007-30272-00-00	UTAH 8-97	Gas Well	P	8	15	S	10	E
43-007-30285-00-00	UTAH 8-98X	Gas Well	P	8	15	S	10	E
43-007-30274-00-00	UTAH 8-99	Gas Well	P	8	15	S	10	E
43-007-30413-00-00	UTAH 9-228	Gas Well	P	9	15	S	9	E
43-007-30414-00-00	UTAH 9-229	Gas Well	P	9	15	S	9	E
43-007-30279-00-00	WILLIAMS 30-78	Gas Well	P	30	14	S	10	E
43-007-30481-00-00	WOOLSTENHULME 05-266	Gas Well	P	5	15	S	10	E
43-015-30250-00-00	UTAH 16-110	Gas Well	Shut In	16	16	S	9	E

DIVISION OF OIL, GAS AND MINING***SPUDDING INFORMATION***Name of Company: CONOCOPHILLIPS COMPANYWell Name: SCHMIDT 29-531Api No: 43-007-30863 Lease Type: FEESection 29 Township 14S Range 10E County CARBONDrilling Contractor PENSE BROTHERS RIG # 9**SPUDDED:**Date 08/11/03Time 11:00 AMHow DRY***Drilling will commence:*** _____Reported by FRANKIE HATHAWAYTelephone # 1-435-613-9777Date 08/11/2003 Signed: CHD

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

007

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> OTHER:	5. Lease Designation and Serial Number: Private
2. Name of Operator: ConocoPhillips Company	6. If Indian, Allottee or Tribe Name: N/A
3. Address and Telephone Number: 6825 S. 5300 W. P.O. Box 851 Price, Utah 84501 (435) 613-9777	7. Unit Agreement Name: Drunkards Wash UTU-67921X
4. Location of Well Footages: 1803' FSL, 2148' FWL QQ, Sec., T., R., M.: NE/4, SW4 Sec. 29, T. 14S, R. 10E, SLB&M	8. Well Name and Number: Schmidt 29-531 9. API Well Number: 43-007-30863 10. Field or Pool, or Wildcat: Drunkards Wash
County: Carbon County State: Utah	

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT (Submit in Duplicate)	SUBSEQUENT REPORT (Submit Original Form Only)
<input type="checkbox"/> Abandon <input type="checkbox"/> Repair Casing <input type="checkbox"/> Change of Plans <input type="checkbox"/> Convert to Injection <input type="checkbox"/> Fracture Treat or Acidize <input type="checkbox"/> Multiple Completion <input type="checkbox"/> Other _____ Approximate date work will start _____	<input type="checkbox"/> New Construction <input type="checkbox"/> Pull or Alter Casing <input type="checkbox"/> Recomplete <input type="checkbox"/> Reperforate <input type="checkbox"/> Vent or Flare <input type="checkbox"/> Water Shut-Off <input checked="" type="checkbox"/> Other _____ Spud Notice Date of work completion _____
<p>Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.</p> <p>* Must be accompanied by a cement verification report.</p>	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Please be advised that the Schmidt 29-531 well was spud on 8/11/03 at 12:00 P.M..
Pense bros. Rig #9
Dry drill

ORIGINAL

RECEIVED

AUG 15 2003

DIV. OF OIL, GAS & MINING

Not Confidential
Per Well File / CHD
CONFIDENTIAL

13.

Name & Signature: <u>Frankie Hathaway</u> <i>Frankie Hathaway</i>	Title: <u>Operations Clerk</u>	Date: <u>8/13/03</u>
---	--------------------------------	----------------------

(This space for state use only)

008

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM - FORM 6

OPERATOR ConocoPhillips Company
ADDRESS 6825 S. 5300 W. P.O. Box 851
Price, UT 84501

OPERATOR ACCT. NO. N2335

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
A	99999	13856	43-007-30879	ANR 27-690	NESE	27	15S	08E	Carbon	8/7/03	8/22/03
WELL 1 COMMENTS: New single well spud outside PA but inside of Unit Boundary <i>outside</i> frsd											
A	99999	13857	43-007-30863	Schmidt 29-531	NESW	29	14S	10E	Carbon	8/11/03	8/22/03
WELL 2 COMMENTS: New single well spud <u>outside</u> PA but inside of Unit Boundary frsd											
A	99999	13858	43-007-30880	ANR 27-689	NESW	27	15S	08E	Carbon	8/4/03	8/22/03
WELL 3 COMMENTS: New single well spud outside PA but inside of Unit Boundary <i>outside</i> frsd											
WELL 4 COMMENTS:											
ORIGINAL											
WELL 5 COMMENTS:											
CONFIDENTIAL											

ACTION CODES (See Instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

RECEIVED

AUG 15 2003

DIV. OF OIL, GAS & MINING

Frankie Hathaway
Signature

Operations Clerk
Title

8/13/03
Date

Phone No. (435) 613-9777

NOTE: Use COMMENT section to explain why each Action Code was selected.

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

009

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL ☐ GAS ☒ OTHER:

2. Name of Operator: ConocoPhillips Company

3. Address and Telephone Number: 6825 S. 5300 W. P.O. Box 851 Price, Utah 84501 (435) 613-9777

4. Location of Well Footages: 1803' FSL, 2148' FWL
QQ, Sec., T., R., M.: NE/4, SW/4 Sec. 29, T. 14S, R. 10E, SLB&M

5. Lease Designation and Serial Number:

Private

6. If Indian, Allottee or Tribe Name:

N/A

7. Unit Agreement Name:

Drunkards Wash UTU-67921X

8. Well Name and Number:

Schmidt 29-531

9. API Well Number:

43-007-30863

10. Field or Pool, or Wildcat:

Drunkards Wash

County: Carbon County

State: Utah

11. **CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA****NOTICE OF INTENT**
(Submit in Duplicate)

- | | |
|--|---|
| <input type="checkbox"/> Abandon | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Recomplete |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Reperforate |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Multiple Completion | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other _____ | |
- Approximate date work will start _____

SUBSEQUENT REPORT
(Submit Original Form Only)

- | | |
|---|---|
| <input type="checkbox"/> Abandon * | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Reperforate |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Other _____ Well Report | |
- Date of work completion _____

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

See Attached:

ORIGINAL**CONFIDENTIAL**

13.

Name & Signature: Frankie Hathaway

Title: Operations Clerk

Date: 8/25/03

(This space for state use only)

RECEIVED**AUG 27 2003**

DIV. OF OIL, GAS & MINING

DRUNKARDS WASH PROJECT

DAILY WELL REPORT

SCHMIDT 29-531

API NO: 43-007-30863

1803' FSL, 2148' FWL

NESW SEC: 29 TWN 14S RNG: 10E

COUNTY: Carbon

ELEVATION: 5608.2

DRILLING CONTRACTOR: Pense Brothers Rig #9

SPUD TIME/DATE: 8/11/2003 12:00:00 PM

TD TIME/DATE: 8/12/2003 7:30:00 PM

TD DEPTH: 1670

ON-LINE TIME/DATE:

Bit Information

Type	Size	In	Out	Hours	Rotating Hours
Air Hammer	15 in	0.00	21.00	1	0.5
Air Hammer	11 in	21.00	290.00	2.5	2
Air Hammer	7 7/8	275.00		22	9.5

Conductor Casing

Bore Hole Size: 15 in Conductor From: 0.00 To: 21.00

Casing Description: 12 3/4in PE Number of Joints: 1 Set @: 21.00

Cement: Amount:

Cement Report:

Surface Casing

Bore Hole Size: 11 in Surface Casing From: 21.00 To: 290.00

Casing Description: 8 5/8 in 24#/ft J-55 Number of Joints: 9 Set @: 275.00

Cement: G + 2%S-1 + 1/4#/sk D-29 Amount: 108.00

Cement Report: r/up cementers, safety mtg, test lines, pump 25bbls ahead, mix & pump cement, displace w/ 15bbls of h2o, close valve @ 4:15pm 8/11/03 5bbls good cement to surface,

Production Casing

Bore Hole Size: 7 7/8 in Prod.Casing From: 275.00 To: 1670.00

Casing Description: 5 1/2 in 17#/ft N-80 Number of Joints: 38 Length: 1618.00

Lead Cement 50/50 POZ, 8%D20, 10%D44, 2%S001, 1/4#/sk Amount: 140.00

Tail Cement: 10-1 RFC Amount: 75.00

Cement Report: r/up cementers, safety mtg, test lines, pump 40bbls ahead, mix & pump cement, s/down, drop plug, displace w/ 37.5bbls of h2o, plug down @

Float Equipment: 5 1/2in float shoe Centralizers ran on: 2,5,9,13, & 21

Drilling Data

DAY 1 8/12/2003

CURRENT DEPTH 290 CURRENT OPERATIONS: n/up bop

ROTATING HRS: 2.50

7am-10am move on location,
10am-12pm r/up service equipment, safety mtg, jsa,
12pm-1pm spud @ 12pm 8/11/03, drill & set 21ft of conductor,
1pm-3:15pm n/up & drill 290ft of 11in hole, pooh,
3:15pm-3:40pm rih w/ 8 5/8in guide shoe + 9jts of 8 5/8in csg, land @ 275ft,
3:40pm-4:15pm r/up cementers, safety mtg, cement surace pipe, close valve @ 4:15pm 8/11/03, 5bbls good cement to surface,
4:15pm-6:30pm r/down cementers, clean up rig, sdfn
6:30pm-7am no activity,

Estimated Daily Cost: [REDACTED]

DAY 2 8/13/2003

CURRENT DEPTH 1670 CURRENT OPERATIONS: rih to bottom,

ROTATING HRS: 9.50

7am-8am n/up bop & manifold,
8am-9am test bop,
9am-10am change bits, rih, drill out cement,
10am-12pm drill to 770ft,
12pm-3pm drill 770-1370ft,
3pm-7:30pm drill 1370-1670ft, td @ 7:30pm 8/12/03,
7:30pm-8:15pm clean hole & pull up to 1000ft (above ferron) & sdfn,

Estimated Daily Cost: [REDACTED]

DAY 3 8/14/2003

CURRENT DEPTH 1670 CURRENT OPERATIONS: r/up to run csg,

ROTATING HRS: 0.00

7am-7:30am safety mtg, rih to bottom, 10ft fill,
7:30am-8:15am pooh,
8:15am-11am r/up loggers, log well r/down loggers, release rig @ 11am 8/13/03,
11am-12pm r/down rig & move to yard,
12pm-3pm no activity,
3pm-6pm move workover on, r/up, set racks, unload & tally csg,
6pm-7am no activity,

Estimated Daily Cost: [REDACTED]

DAY 4 8/15/2003

CURRENT DEPTH 1618 CURRENT OPERATIONS: no activity,

ROTATING HRS: 0.00

7am-8am safety mtg, prep to run csg,
8am-9am rih w/ 5 1/2in float shoe + 38jts of csg, land @ 1618.45ft,
9am-9:30am r/up cementers, safety mtg,
9:30am-10:05am cement longstring, plug down @ 10:05am 8/14/03, 7bbls good cement to surface,
10:05am-11am r/down cementers, sdfn

Estimated Daily Cost: [REDACTED]

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

010

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL ☐ GAS ☒ OTHER:

2. Name of Operator: ConocoPhillips Company

3. Address and Telephone Number: 6825 S. 5300 W. P.O. Box 851 Price, Utah 84501 (435) 613-9777

4. Location of Well
Footages: 1803' FSL, 2148' FWL
QQ, Sec., T., R., M.: NE/4 SW/4 Section 29, T14S, R10E, SLB&M

5. Lease Designation and Serial Number:

Private

6. If Indian, Allottee or Tribe Name:

N/A

7. Unit Agreement Name:

Drunkards Wash UTU-67921X

8. Well Name and Number:

Schmidt 29-531

9. API Well Number:

43-007-30863

10. Field or Pool, or Wildcat:

Drunkards Wash

County: Carbon County

State: Utah

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

NOTICE OF INTENT (Submit in Duplicate)

- | | |
|--|---|
| <input type="checkbox"/> Abandon | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Recomplete |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Reperforate |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Multiple Completion | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other _____ | |
- Approximate date work will start _____

SUBSEQUENT REPORT (Submit Original Form Only)

- | | |
|--|---|
| <input type="checkbox"/> Abandon * | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Casing |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Reperforate |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Other <u>1st Production Notification</u> | |
- Date of work completion _____

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Please be advised that the Schmidt 29-531 showed first production on: 9/22/03
Gas production: 74 mcf
Water production: 578 bbl

ORIGINAL

CONFIDENTIAL

13.

Name & Signature: Frankie Hathaway *Frankie Hathaway* Title: Operations Clerk Date: 10/3/03

(This space for state use only)

OCT 09 2003

DIV. OF OIL, GAS & MINING

RECEIVED

FORM 8

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

NOV 03 2003

011

DIV. OF OIL, GAS & MINING

5. LEASE DESIGNATION AND SERIAL NO.

Private

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

N/A

7. UNIT AGREEMENT NAME

Drunkards Wash UTU-67921X

8. FARM OR LEASE NAME

Schmidt

9. WELL NO.

29-531

10. FIELD AND POOL, OR WILDCAT

Drunkards Wash

11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA

NE/4, SW/4, Sec. 29, T14S, R10E
SLB&M

12. COUNTY

Carbon

13. STATE

Utah

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL:

OIL
WELL ☐GAS
WELL ☒DRY ☐

Other

b. TYPE OF COMPLETION:

NEW
WELL ☒WORK
OVER ☐DEEP-
EN ☐PLUG
BACK ☐DIFF.
RESVR. ☐

Other

2. NAME OF OPERATOR

ConocoPhillips Company

3. ADDRESS OF OPERATOR

6825 S. 5300 W. P.O. Box 851 Price, Utah 84501 (435) 613-9777

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)

At surface 1803' FSL, 2148' FWL

At top prod. interval reported below

At total depth

14. API NO

43-007-30863

DATE ISSUED

9/4/02

15. DATE SPUDDED

8/11/03

16. DATE T.D. REACHED

8/12/03

17. DATE COMPL.

9/21/03

(Ready to
or
(Plug & Abd.)

18. ELEVATIONS (DF, REB, RT, GR, ETC.)

5608'

19. ELEV. CASINGHEAD

N/A

20. TOTAL DEPTH, MD & TVD

1670'

21. PLUG BACK T.D., MD & TVD

1618'

22. IF MULTIPLE COMPL.,

HOW MANY

N/A

23. INTERVALS

DRILLED BY

ROTARY TOOLS

to TD

CABLE TOOLS

N/A

24. PRODUCING INTERVAL(S), OF THIS COMPLETION--TOP, BOTTOM, NAME (MD OR TVD)

Ferron Coal - Top Coal 1246' & Bottom Coal 1352'

25. WAS

DIRECTIONAL

SURVEY MADE

26. TYPE ELECTRIC AND OTHER LOGS RUN

Dual Induction, Laterolog, SFF, Caliper, Comp Density & Neutron

27. WAS WELL CORED

YES ☐NO ☒

DRILL STEM TEST

YES ☐NO ☒

(Submit analysis)

(See reverse side)

28. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENT RECORD	AMOUNT PULLED
12 3/4"	Conductor	21'	15"		
8 5/8"	24#	275'	11"	108 sks Class G, 2%, 4% Gell & 1/4#/sk Floccel	
5 1/2"	17#	1618'	7 7/8"	140 sks 50/50 POZ, 8% D-20, 10% D-44, 2% S-1	
				75 sks 10-1 RFC (Thixotropic)	

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET
					2-7/8"	1437'	N/A

31. PERFORATION RECORD (Interval, size and number)

Ferron Coal

Upper Ferron: 1246'-1262'

4spf .51"

U. Middle Ferron: 1319'-1326'

4spf .51"

Middle Ferron: 1281'-1286', 1291'-1300'

4spf .51"

Lower Ferron: 1338'-1352'

4spf .51"

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
Upper 1246-1262	98200#, 20/40; 10600#, 16/30; 39296 gal fluid
U. Middle 1319-1326	
Middle 1281-1300	6000#, 20/40; 15000#, 16/30; 16529 gal fluid
Lower 1338-1352	12100#, 20/40; 81700#, 16/30; 42978 gal fluid
	12100#, 20/40; 71400#, 16/30; 41779 gal fluid

33. PRODUCTION

DATE FIRST PRODUCTION 9/22/03		PRODUCTION METHOD (Flowing, gas lift, pumping---size and type of pump) Pumping - PC 200-2100					WELL STATUS (Producing or shut-in) Producing	
DATE OF TEST 9/22/03		HOURS TESTED 24hrs.	CHOKE SIZE -----	PROD'N. FOR TEST PERIOD →	OIL---BBL. N/A	GAS---MCF. 74	WATER---BBL. 578	GAS-OIL RATIO
FLOW. TUBING PRESS. 132		CASING PRESSURE 124	CALCULATED 24-HOUR RATE →	OIL---BBL. N/A	GAS---MCF. 74	WATER---BBL. 578	OIL GRAVITY - API (CORR.) N/A	

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

SOLD

TEST WITNESSED BY
Kevin E. Snow

35. LIST OF ATTACHMENTS

36 I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED Kevin Snow *Kevin E. Snow*

TITLE Operations Superintendent

DATE 10/31/03

See Spaces for Additional Data on Reverse Side

WELL NUMBER: Utah 29-531

37 SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof, cored intervals; and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries):				38. GEOLOGIC MARKERS		
FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	TOP MEAS DEPTH	TRUE VERT. DEPTH
Ferron	1280'	1351'	Coals and Sandstones Coal Interval: 1280'-1351'	Blue Gate Bentonite	1081'	
				Tununk Shale	1487'	
				Ferron Sandston	1238'	

ORIGINAL

012

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, deepen existing wells, or to reenter plugged and abandoned wells.
Use APPLICATION FOR PERMIT TO DRILL OR DEEPEN form for such proposals.

1. Type of Well: OIL ☐ GAS ☒ OTHER:

2. Name of Operator:

ConocoPhillips Company

3. Address and Telephone Number:

6825 South 5300 West, P.O. Box 851, Price, UT 84501 (435) 613-9777

4. Location of Well
Footages:

1803' FSL, 2148' FWL

QQ, Sec., T., R., M.:

NE/4, SW/4, SEC. 29, T14S, R10E, SLB & M

5. Lease Designation and Serial Number:

Private

6. If Indian, Allottee or Tribe Name:

N/A

7. Unit Agreement Name:

UTU67921X Drunkards Wash

8. Well Name and Number:

Schmidt 29-531

9. API Well Number:

43-007-30863

10. Field or Pool, or Wildcat:

Drunkards Wash

County: Carbon County

State: Utah

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA**NOTICE OF INTENT**
(Submit in Duplicate)

- | | |
|--|--|
| <input type="checkbox"/> Abandon | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Csg |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Recomplete |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Reperforate |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Multiple Completion | <input type="checkbox"/> Water Shut-Off |
| <input type="checkbox"/> Other _____ | |

Approximate date work will start _____

SUBSEQUENT REPORT
(Submit Original Form Only)

- | | |
|---|--|
| <input type="checkbox"/> Abandon * | <input type="checkbox"/> New Construction |
| <input type="checkbox"/> Repair Casing | <input type="checkbox"/> Pull or Alter Csg |
| <input type="checkbox"/> Change of Plans | <input type="checkbox"/> Reperforate |
| <input type="checkbox"/> Convert to Injection | <input type="checkbox"/> Vent or Flare |
| <input type="checkbox"/> Fracture Treat or Acidize | <input type="checkbox"/> Water Shut-Off |
| <input checked="" type="checkbox"/> Other <u>Chemical/Flush Treatment</u> | |

Date of work completion 05/25/2004

Report results of Multiple Completions and Recompletions to different reservoirs on WELL COMPLETION OR RECOMPLETION REPORT AND LOG form.

* Must be accompanied by a cement verification report.

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

Please be advised that the above referenced well was chemically treated with 4410 gallons of Coalstim fluid on 05/25/2004.

13.

Name & Signature: Lynnette AllredTitle: Sr. Operations AssistantDate: 07/07/2004

(This space for state use only)

RECEIVED

JUL 14 2004

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 6

ENTITY ACTION FORM

Operator: ConocoPhillips Operator Account Number: N 2335
Address: 6825 South 5300 West
city Price
state UT zip 84501 Phone Number: (435) 613-9777

Well 1

API Number	Well Name		QQ	Sec	Twp	Rng	County
4300730845	PMC 10-526		SWSE	10	15S	08E	CARBON
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
C	13634	11256				11/9/05	
Comments: Well was converted to PA on 11/01/2002 <div style="display: flex; justify-content: space-between;"> FRSD -K </div>							

Well 2

API Number	Well Name		QQ	Sec	Twp	Rng	County
4300730888	PIERCE 32-438		NWSE	32	14S	10E	CARBON
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
C	14184	11256				11/9/05	
Comments: Well was converted to PA on 07/01/2004. <div style="display: flex; justify-content: space-between;"> FRSD -K </div>							

Well 3

API Number	Well Name		QQ	Sec	Twp	Rng	County
4300730863	SCHMIDT 29-531		NESW	29	14S	10E	CARBON
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
C	13857	11256				11/9/05	
Comments: Well was converted to PA on 07/01/2003 <div style="display: flex; justify-content: space-between;"> FRSD -K </div>							

ACTION CODES:

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

Lynnette Allred

Name (Please Print)

L. Allred

Signature

Sr. Operations Assistant

11/9/2005

Date

NOV 14 2005

DIV. OF OIL, GAS & MINING

RECEIVED

NOV 09 2005

DIV. OF OIL, GAS & MINING

e-mail



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

IN REPLY REFER TO
UT-922

May 5, 2004

ConocoPhillips Company
Attn: Gregory A. Reeves
P.O. Box 2197
Houston, Texas 77252-2197

Re: 6th Revision Consolidated Ferron Formation
Participating Area "A,C,D"
Drunkards Wash Unit
Carbon and Emery Counties, Utah

Gentlemen:

The 6th Revision Consolidated Ferron Formation Participating Area "A,C,D", Drunkards Wash Unit, UTU67921F, is hereby approved effective as of July 1, 2003, pursuant to Section 11 of the Drunkards Wash Unit Agreement, Carbon and Emery Counties, Utah.

The 6th Revision Consolidated Ferron Formation Participating Area "A,C,D" results in the addition of 640.00 acres to the participating area for a total of 69,222.87 acres and is based upon the completion of the following wells, as capable of producing unitized substances in paying quantities.

WELL NO.	API NO.	LOCATION	LEASE NO.
Utah 19-532	43-007-30891	NE, 19-14S-10E	State
29-548	43-007-30864	NW, 29-14S-10E	Fee
29-549	43-007-30865	SE, 29-14S-10E	Fee
29-531	43-007-30863	SW, 29-14S-10E	Fee

Copies of the approved request are being distributed to the appropriate agencies and one copy is returned herewith. Please advise all interested parties of the approval of the 6th Revision Consolidated Ferron Formation Participating Area "A,C,D", Drunkards Wash Unit and the effective date.

Sincerely,

/s/ Terry Catlin

Terry Catlin
Acting Chief, Branch of Fluid Minerals

Enclosure

RECEIVED

MAY 10 2004

DIV. OF OIL, GAS & MINING